

Project Info

Project Description

Construction of a one-story 1,295 ft² single family residence, driveway, decks, septic system, and landscaping improvements, on an infill parcel where a previous residence owned by the family was destroyed by fire.

All County and LCP building height, yard setback, and FAR limits are complied with, as well as all FEMA base elevation and design standards. A two-bedroom residence previously existed on the property until it was destroyed by a fire in 1983. The applicant's family has continuously owned the property since the 1930s.

Applicant	Address	APN	Lot Area
Brian & Alyce Johnson	P.O. Box 1139 Homewood, CA 96141	195-162-49	15,200 Ft (0.36) Acres

Zoning	Construction Type	FEMA Flood Zones
C-R2 - Residential, Two Family	VA	VE, A0

Square Footage (Proposed)	Footprint (Proposed)	FAR (Proposed)	FAR (Maximum)
1,296	1,296	0.08	0.3

Average Slope	Driveway Slope	Minimum Parking Spaces	Proposed Parking Spaces
7.13%	12% Maximum	2 spaces	2 spaces

Minimum Setbacks for Residence	Proposed Setbacks for Residence	Maximum Heights	Proposed Heights
Front: 25'	Front: 25'	Residence: 25'	Residence: 20' 7"
Rear: 16'	Rear: 16'	Retaining Wall: 4'	Retaining Wall: 4'
Side: 6'	Side: 46'/100'	Boundary Fence: 6'	Boundary Fence: 6'
Rear Deck: 10'	Rear Deck: 10'	Latitude:	Longitude
Front Porch: 19'	Front Porch: 19'	37.899	-122.645

Sheet Index

1	Project Info + Site Plan
2	Foundation + Floor Plan
3	Elevations
4	Sections + Landscaping Plan
5	Exterior Materials
C1	Title Sheet
C2	Grading Plan
C3	Drainage Plan
C4	Erosion & Sediment Control Plan

Consultant Info

Design	Civil Engineer	Structural Engineer
CivicKnit	AYS Engineering Group, Inc	Paul Krohn, PE
Steve Kinsey (415) 307-1370	Troy Pearce (707) 763-6220	(530) 342-2926
P.O. Box 81 Forest Knolls, CA 94933	P.O. Box 5693 Petaluma, CA 94955	P.O. Box 113 Fairfax, CA 94978

Coastal Engineer	Geotechnical Engineer	Surveyor
Noble Consultants, Inc	Murray Engineers, Inc	L.A. Stevens & Associates, Inc
Ron Noble (415) 884-0727	Christopher Korth (415) 888-8952	Larry Stevens (415) 382-7713
2420 Mountain Ranch Rd. Petaluma, CA 94954	409 4th St, San Rafael, CA 94901	7 Commercial Blvd. Novato, CA 94949


Vicinity Map




Directions

Turn left onto Calle Del Onda going Northbound on Highway 1. The property is the last lot on the left side of the street.


Site Plan



Fence Details




Roofing Plan



1	Revisions	Drawn By	Date
6/10/22	# Description		


Project Info

21 Calle del Onda Revised Design




CivicKnit
P.O. Box 81
Forest Knolls
94933
415.488.4193

Floor Plan




Foundation Plan




FOUNDATION DESIGN TO REFLECT RECOMMENDATIONS OF GEOTECHNICAL ENGINEERING EVALUATION

Revisions #	Description	Drawn By	Date


North




East




West




South




Revisions #	Description	Drawn By	Date




Section A



Section B



Landscaping Plan




Plant Species

#	Latin Name	Common Name	California Native	Notes
1	<i>Festuca rubra, Trifolium wildenovii</i>	Native Lawn Grasses and Clover	✓	Native grass lawn to cover entirety of wastewater dispersal area
2	<i>Calamagrostis foliosa</i>	Reed Grass	✓	
3	<i>Festuca californica</i>	California Fescue	✓	Plant bunches along perimeter of driveway and deck every 2 - 3 feet
4	<i>Clematis lasiantha</i>	Chapparral Clematis	✓	
5	<i>Echium vulgare</i>	Viper's Bugloss		
6	<i>Cistus creticus</i>	Rock Rose		
7	<i>Escallonia Rubra</i>			

Revisions #	Description	Drawn By	Date

Siding




Exterior siding will be HardieShingle Night Gray fiber cement shake siding

Roofing



Asphalt composite shingles will be used on all pitched roof areas

Fencing




Redwood fencing will be used around the perimeter of the septic area and the rear yard. In some locations these wooden fences will sit atop concrete retaining walls

Lighting Fixtures



Exterior lighting will consist of recessed soffit lights and hooded down lights to minimize light pollution

Decking, Stairs & Railing




Clamshell colored Trex composite material will be used for all decks, railings, and stairs

Windows






Frost colored Milgard fiberglass clad windows will be used at all locations

Revisions #	Description	Drawn By	Date




NOTE
STRUCTURAL DESIGN OF WALLS
BY OTHERS




LEGEND

- 1.5 FILL DEPTH (FT.)
- 1.3 CUT DEPTH (FT.)
- 1.0 WALL HEIGHT (FT.)



RET. WALL HTS DETAIL



DRIVEWAY PROFILE


EARTHWORK QUANTITIES
 CUT 52.0 CY
 FILL 118.0 CY
 NET 66.0 CY IMPORT(FILL)



GRADING PLAN C2

<p>Revisions:</p> <table border="1"> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> </table>													<p>PREPARED FOR: Brian Johnson PO Box 1139, Homewood, CA 96141</p>
<p>IMPROVEMENT PLAN 21 CALLE DEL ONDA Stinson Beach, CA APN 195-162-49</p>	<p>Engineering Group, Inc PO Box 5693, Petaluma, CA 94955 Voice (707) 763-6620</p>												
<p>Job No. 2018-038 Date 10-1-20 Drawn By: TKP Checked By: TKP Scale as shown</p>	<p>Sheet 2 of 6</p>												


BACK FROM HIGHEST TIDE SINCE JANUARY 2011 OF 7.8' LOCATED ON 7/17/2015
 (AMBIGUOUS LINE SUBJECT TO CHANGE)



LEGEND

- HYDROSEED/MULCH WOOD CHIPS OR EROSION CONTROL BLANKET ALL DISTURBED AREAS BEFORE RAIN
- WATTLES
- AREA OF DISTURBANCE= 6700 SQ FT
0.15 ACRES
- EROSION CONTROL BLANKET FOR CHANNEL FLOW

LEGEND
1/8" = 1'-0"




NOTE:
MULCH TO BE BLOWN ONTO EXPOSED EARTH. ANCHOR MULCH USING A TACKIFIER OR BY MECHANICAL MEANS. APPLY AT A RATE OF 4000LBS/ACRE OR USING MANUFACTURER'S RECOMMENDATIONS. MAY ALSO BE HAND MULCHED WITH STRAW TO A DEPTH OF 1" MIN OVER ALL BARE GROUND.

EROSION CONTROL NOTES

- 1) BOUNDARY FOR REFERENCE PURPOSES ONLY NOT TO BE USED AS BOUNDARY SURVEY.
- 2) ALL MODIFICATIONS TO THIS PLAN AND ALL EROSION CONTROL REPAIRS SHALL BE NOTED ON THIS PLAN AND KEPT UPDATED BY THE CONTRACTOR IN THE FIELD DURING CONSTRUCTION.
- 3) ALL EROSION CONTROL MEASURES SHALL BE REGULARLY MONITORED AND REPLACED IF NECESSARY.
- 4) ALL EROSION CONTROL MEASURES SHALL BE CHECKED AND THEIR OPERATION VERIFIED AFTER STORM EVENTS.
- 5) NO SILT LADEN WATER SHALL LEAVE SITE.
- 6) ANY MATERIAL OR DEBRIS STOCKPILED ON SITE SHALL BE CONTAINED BY WATTLES AND COVERED.
- 7) A GRAVEL ACCESSWAY AT LEAST 40' LONG SHALL BE MAINTAINED AT DRIVEWAY ENTRANCE. 6" OF GRAVEL MUST BE MAINTAINED IN THIS AREA AND WILL REQUIRE REPLENISHMENT OVER THE COURSE OF CONSTRUCTION.
- 8) AS PART OF THE MONITORING, ANY SILT THAT BUILDS UP BEHIND THE WATTLES SHALL BE REMOVED.
- 9) MINIMIZE THE AMOUNT OF MATERIAL STOCKPILED ON SITE.
- 10) ANY EXCAVATED MATERIAL STOCKPILED ON SITE SHALL BE COVERED WITH 15 MIL PLASTIC AND THE ENDS HELD DOWN WITH SAND BAGS.
- 11) ADDITIONAL SAND BAGS, WATTLES AND OTHER EROSION CONTROL MATERIAL SHALL BE STORED ON SITE TO ALLOW FOR IMMEDIATE REPAIR OF PROPOSED FACILITIES.
- 12) A WATTLE DIKE SHALL BE INSTALLED ON THE PROPOSED DRIVEWAY ROUGH GRADE EVERY 10' OF VERTICAL SEPARATION OR MORE OFTEN AS NEEDED TO PREVENT EROSION OF THE PROPOSED DRIVEWAY.
- 13) REMOVE SEDIMENT WHEN ACCUMULATION REACHES 1/2 OF THE BARRIER HEIGHT.
- 14) MINIMIZE THE AMOUNT OF EARTHWORK EXPOSED AT ANY ONE TIME.
- 15) INSTALL DRIVEWAY GRAVEL BASE COURSE AS SOON AFTER ROUGH GRADING AS POSSIBLE.
- 16) PRIOR TO PLACING AC ON ROADWAY OR DRIVEWAY, DRIVEWAYS TO BE USED FOR CONCRETE WASHDOWN. ONCE THE DRIVEWAY IS COMPLETE, USE A DESIGNATED CONCRETE WASH DOWN AREA.
- 17) HYDROSEED ALL EXPOSED AREAS OF EARTH PRIOR TO START OF RAINY SEASON. IF RAIN IS IMMINENT OR GRASS IS NOT MATURE PRIOR TO OCTOBER 15 COVER EXPOSED EARTH WITH STRAW & TACKIFIER.
- 18) THE ACTUAL AMOUNT AND TYPES OF EROSION CONTROL DEVICES WILL VARY BASED ON CONSTRUCTION METHODOLOGIES AND STAGING. THIS PLAN SHOWS A MINIMUM REQUIREMENT AND SHOULD BE SUPPLEMENTED AS NEEDED.


EROSION & SEDIMENT CONTROL PLAN

SCALE 1"=20'



STABILIZED ENTRANCE

SCALE 1"=10'



WATTLE INSTALLATION

SCALE 1"=10'

EROSION & SEDIMENT CONTROL PLAN

<p>Revisions:</p> <p>1. 5-18-22</p>	
<p>PREPARED FOR:</p> <p>Brian Johnson PO Box 1139, Homewood, CA 96141</p>	<p>IMPROVEMENT PLAN</p> <p>21 CALLE DEL ONDA Stinson Beach, CA APN 195-162-49</p>
<p>AYS Engineering Group, Inc PO Box 5693, Petaluma, CA 94955 Voice (707) 763-6620</p>	<p>Job No. 2018-038 Date 10-1-20 Drawn By: TKP Checked By: TKP Scale as shown</p>
<p>Sheet 4 of 6</p>	

C4


03BA-210nda G&D - Johnson\dwg\5-4-22-grading and drainage.dwg, C4-EROSION CONTROL, 5/26/2022 12:30:08 PM.

NOTE:
REROUTE ANY WATERLINE WITHIN TEN FEET OF SEPTIC SYSTEM IF CROSSING OF WATER AND SEWER LINES MUST BE MADE THEN SLEEVE BOTH WATER AND SEWER WITHIN TEN FEET EACH OF EACH OTHER WITH SCH 80 PVC

CONCRETE RETAINING WALL BELOW GRADE TO PROTECT SEPTIC AND SUMP TANKS. STRUCTURAL ENGINEER TO DESIGN TO WITHSTAND WAVE RUNUP FORCES

NOTE:
PROVIDE 115 VOLT SINGLE PHASE POWER SOURCE. ELECTRICIAN TO PROVIDE A MINIMUM OF 20 AMPS TO THE CONTROL PANEL.

NOTE:
SANDFILTER MONITORING WELLS #1 AND #3 TO BE INSTALLED TO THE UPPER GRAVEL/SAND INTERFACE AND #2 AND #4 TO THE BOTTOM OF THE LINER



SEPTIC SYSTEM LAYOUT
SCALE 1"=10'


NOTE:
LOCATION OF EXISTING UTILITIES IS UNKNOWN AND MUST BE DETERMINED BY CONTRACTOR PRIOR TO CONSTRUCTION. ENGINEER ASSUMES NO RESPONSIBILITY IN LOCATING EXISTING UTILITIES.

NOTE:
PROVIDE CONCRETE THRUST BLOCKS AT PIPE DIRECTION CHANGES OF GREATER THAN 15 DEGREES. SEE DETAIL FOR THRUST BLOCKS.


SAND FILTER MEDIA SIEVE ANALYSIS

SIZE	% PASSING
#4	100
#8	70-90
#16	40-60
#30	25-35
#50	2-5
#60	0


D10>0.400mm
D60>1.4mm
Uc 3.0 - 4.0




SAND FILTER SECTION D-D ALONG 15.0 FOOT DIMENSION
SCALE 1"=10'



SAND FILTER SECTION C-C ALONG 8.5 FOOT DIMENSION
SCALE 1"=10'




MONITORING WELL DETAIL
NTS




SAND FILTER
SCALE 1"=10'

- GENERAL NOTES
- 1) CONTRACTOR TO NOTIFY STINSON BEACH COUNTY WATER DISTRICT (SBCWD) PERSONEL AND DESIGN ENGINEER 48 HOURS PRIOR TO BEGINNING CONSTRUCTION.
 - 2) TOPOGRAPHIC SURVEY PROVIDED BY L.A. STEVENS AND ASSOC. 415-382-7713
 - 3) NOT TO BE USED AS A BOUNDARY SURVEY- SURVEYOR TO STAKE ALL PROPERTY LINES AND EASEMENTS.
 - 4) MAINTAIN 10' SEPARATION FOM ANY SEWAGE LINE TO WATERLINE IF NOT POSSIBLE REROUTE TO MAINTAIN SEPARATION. CROSSING SHALL BE MADE WITH WATER ABOVE SEWER LINE WITH A 1' SEPARATION AND CONCRETE BETWEEN LINES.
 - 5) NO CUTS SHALL BE MADE DOWNSLOPE OF DRAINFIELD WITHOUT PERMISSION OF BOTH SBCWD AND DESIGN ENGINEER.
 - 6) CONSULT ENGINEER PERTAINING TO LANDSCAPING IN SEPTIC SYSTEM AREA.
 - 7) NO MATERIAL SUBSTITUTION WITH OUT DESIGN ENGINEER APPROVAL.
 - 8) NO WORK TO BE PERFORMED DURING WET CONDITIONS AND ALL EXCAVATION TO BE COORDINATED WITH THE DESIGN ENGINEER AND SBCWD
 - 9) ALL TANKS TO BE WATERTIGHT-SEE WATERTIGHTNESS TEST.
 - 10) CONTRACTOR NOT TO OVEREXCAVATE THE DELIVERY LINE TRENCH/S MAXIMUM DEPTH OF TRENCH IS 24 INCHES.



VICINITY MAP
NO SCALE



OVERALL PROPERTY
SCALE 1"=30'

- 11) EROSION PROTECTION SHALL BE PLACED IN ALL DISTURBED AREAS. STRAW AND SEED SHALL BE PLACED AT A MINIMUM PRIOR TO FINAL INSPECTION.
- 12) ALL PLUMBING FIXTURES TO BE LOW FLOW 1.6 GAL FLUSH TOILETS AND 2 GAL/MIN SHOWER HEADS.
- 13) ALL SEWER LINES FROM BUILDINGS SHALL BE 4 INCH SCH 40 PVC OR APPROVED EQUIVALENT WITH A MINIMUM SLOPE OF 2 PERCENT. INSTALL CLEANOUTS AT CHANGES IN DIRECTION AND 5 FEET FROM THE OUTSIDE OF THE BUILDING.
- 14) ALL WORK SHALL BE IN CONFORMANCE WITH THESE PLANS AND THE MOST RECENT REGULATIONS FOR WASTEWATER SYSTEMS SBCWD.
- 15) CONTRACTOR TO KEEP A COUNTY STAMPED SET OF PLANS AT THE JOBSITE AND A SET WITH ALL AS BUILT CHANGES MARKED UP AT THE JOB SITE AT ALL TIMES. THE CONTRACTOR TO PROVIDE ONE COPY OF THESE CHANGES ON A PLAN FOR PREPARATION OF AS-BUILT DRAWINGS TO GAIN SBCWD FINAL APPROVAL.

Revisions:

PREPARED FOR:
Brian Johnson
PO Box 1139
Homewood, CA 96141

RAISED BED/SAND FILTER SYSTEM
21 CALLE DEL ONDA
Stinson Beach, CA
APN 195-162-49


AYS Engineering Group, Inc
PO Box 5693, Petaluma, CA 94955
Voice (707) 763-6620, Fax (707) 781-8061

Job No. 2018-038
Date 11-19-18
Drawn By: tkp
Checked By: tkp
Scale as shown

Sheet 1 of 2


1






No.	DIAMETER	PERF SIZE	LENGTH	# OF PERFS"
A1	1 1/4"	1/8"	21'	10
A2	1 1/4"	1/8"	21'	10
A3	1 1/4"	1/8"	21'	10
B1	1 1/4"	1/8"	21'	10
B2	1 1/4"	1/8"	21'	10
B3	1 1/4"	1/8"	21'	10


LATERAL SCHEDULE
NOT TO SCALE



DIVERSION VALVE BOX DETAIL
NOT TO SCALE




SECTION A-A ALONG RAISED BED DRAINFIELD
NTS




SECTION B-B ALONG RAISED BED DRAINFIELD
NTS


- TANK WATER TIGHTNESS TEST**
- CAP OR TEST PLUG ALL INLETS AND OUTLETS TO TANK.
 - FILL TANK WITH WATER TWO INCHES INTO THE RISER AND MARK WATER LEVEL. SCHEDULE WITH ENGINEER AND NCM 24 HOURS BEFORE FILLING TANK.
 - IF AFTER 24 HOURS WATER LEVEL DROPS, TANK MUST BE MADE WATER TIGHT BY APPLYING WATERPROOF SEALER (NOT BITUMINOUS PRODUCT) THOROPUG, THOROSEAL OR OTHER PORTLAND CONCRETE CEMENT PRODUCT.



VALVE BOX DETAIL
NOT TO SCALE



2000 GALLON TRAFFIC RATED SEPTIC TANK DETAIL (TYP.)
NOT TO SCALE



PS#1 and #2 2000 GALLON TRAFFIC RATED COMBO SUMP TANK DETAIL
NOT TO SCALE

GENERAL NOTES

- CONTRACTOR TO NOTIFY STINSON BEACH COUNTY WATER DISTRICT (SBCWD) PERSONEL AND DESIGN ENGINEER 48 HOURS PRIOR TO BEGINNING CONSTRUCTION.
- NOT TO BE USED AS A BOUNDARY SURVEY- SURVEYOR TO STAKE ALL PROPERTY LINES AND EASEMENTS. SURVEY PROVIDED BY LAWRENCE P DOYLE 415-388-9585
- MAINTAIN 10' SEPARATION FROM ANY SEWAGE LINE TO WATERLINE IF NOT POSSIBLE REROUTE TO MAINTAIN SEPARATION. CROSSING SHALL BE MADE WITH WATER ABOVE SEWER LINE WITH BOTH LINES SLEEVED WITHIN 10' OF EACH OTHER.
- NO CUTS SHALL BE MADE DOWNSLOPE OF DRAINFIELD WITHOUT PERMISSION OF BOTH SBCWD AND DESIGN ENGINEER.
- CONSULT ENGINEER PERTAINING TO LANDSCAPE SEPTIC SYSTEM.
- NO MATERIAL SUBSTITUTION WITH OUT DESIGN ENGINEER APPROVAL.
- ALL TANKS TO BE WATER TIGHT-SEE WATER TIGHTNESS TEST.
- CONTRACTOR NOT TO OVEREXCAVATE THE DELIVERY LINE TRENCH/S. MAXIMUM DEPTH OF TRENCH IS 24 INCHES.
- THIS SYSTEM CALLS FOR A DIVERSION VALVE/S WHICH ARE TO BE HOUSED IN A SUBSTANTIAL VALVE BOX. THE BOX IS TO BE EXTENDED TO 3 INCHES ABOVE GRADE. THE VALVE SHOULD BE ALTERNATED EVERY SIX MONTHS.
- EROSION PROTECTION SHALL BE PLACED IN ALL DISTURBED AREAS. STRAW AND SEED SHALL BE PLACED AT A MINIMUM PRIOR TO FINAL INSPECTION.
- ALL SEWER LINES FROM BUILDINGS SHALL BE 3 INCH SDR 35 OR APPROVED EQUIVALENT WITH A MINIMUM SLOPE OF 2 PERCENT. INSTALL CLEANOUTS AT CHANGES IN DIRECTION AND 5 FEET FROM THE OUTSIDE OF THE BUILDING.
- ALL WORK SHALL BE IN CONFORMANCE WITH THESE PLANS AND THE MOST RECENT SBCWD REGULATIONS FOR WASTEWATER SYSTEMS.
- CONTRACTOR TO CONDUCT SQUIRT TEST CONSISTING OF PRESURIZING THE LEACHFIELD WITH THE PUMP AND ADJUSTING THE LEACHFIELD GATE VALVES TO PROVIDE A 5' HIGH STREAM OF WATER THROUGH ORIFICES. THIS IS TO BE REPEATED FOR CONSTRUCTION INSPECTION PHASE 2.
- CONTRACTOR TO KEEP A PLAN SET WITH ALL CHANGES MARKED UP AT THE JOB SITE AT ALL TIMES. THE CONTRACTOR TO PROVIDE ONE COPY OF THESE CHANGES ON A PLAN FOR PREPARATION OF AS- BUILT DRAWINGS TO GAIN COUNTY FINAL APPROVAL.

CONSTRUCTION INSPECTION NOTES
CONTRACTOR TO NOTIFY DESIGN ENGINEER AND SBCWD A MINIMUM OF 48 HOURS PRIOR TO CONSTRUCTION AND INSPECTION OF THE SYSTEM. ADDITIONAL FEES WILL BE REQUIRED BY SBCWD AFTER THREE SITE INSPECTIONS. ENGINEER AND SBCWD SHALL INSPECT THE SYSTEM AT CRITICAL CONSTRUCTION PHASES AS FOLLOWS:

- PHASE ONE:**
- INSPECT STAKE OUT LOCATION OF LATERALS ALONG CONTOURS, THE SEPTIC AND SUMP TANKS, AND THE SAND FILTER.
 - INSPECT THE LEACHLINE GRAVEL AND SAND FILTER MEDIA, AND PROVIDE A CERTIFIED COPY OF WET SIEVE ANALYSIS USING ASTM C-117 OR EQUIVALENT.
- PHASE TWO:**
- INSPECT LEACHLINE INSTALLATION AND LEVEL VIA OPEN TRENCHES AND INSTALLED INSPECTION WELLS.
 - INSPECT PERFORATION SIZE AND SPACING.
 - INSPECT WATER TIGHTNESS OF ALL TANKS.
 - INSPECT SQUIRT TEST OF LEACHFIELD.
 - INSPECT CONTROL PANEL, FLOATS AND CIRCUIT BREAKER FOR ENTIRE SEPTIC SYSTEM.
- PHASE THREE:**
- INSPECT ANY ITEMS LISTED ABOVE WHICH HAVE NOT BEEN OBSERVED YET.
 - INSPECT FINISHED SEPTIC SYSTEM INCLUSIVE OF ANY NECESSARY EROSION CONTROL MEASURES.
 - INSPECT FLOOR PLAN OF STRUCTURE BEING SERVED BY THE SEPTIC SYSTEM. INSPECT, IF APPLICABLE, WHETHER LOW FLOW FIXTURES WERE INSTALLED OR NOT.
 - PROVIDE SBCWD WITH BUILDING DEPARTMENT APPROVAL OF PUMP INSTALLATION.


OPERATION AND MAINTENANCE OF A SEPTIC SYSTEM

- INSPECT SEPTIC TANKS AND DRAINFIELD EVERY SIX MONTHS.
 - IF SLUDGE OR SCUM BUILDUP IS GREATER THAN 6 TO 8 INCHES HAVE TANK PUMPED. (USUAL FREQUENCY FOR PUMPING IS 3 TO 5 YEARS).
 - MINIMIZE THE USE OF GARBAGE DISPOSAL.
 - MINIMIZE THE USE OF HARSH CHEMICALS IN LARGE QUANTITIES.
 - MINIMIZE THE AMOUNT OF GREASE DISPOSED OF IN SINKS. PACKAGE ALL FOOD WASTES AND DISPOSE OF IN GARBAGE FOR SANITARY LANDFILL.
 - MINIMIZE DISPOSAL OF NON-SEWAGE ITEMS SUCH AS SANITARY NAPKINS, CIGARETTES AND OTHERS.
 - MAINTAIN ALL PUMPING. LEAKS SHOULD BE FIXED AS QUICK AS THEY OCCUR.
 - MINIMIZE LIQUID LOAD ON THE SYSTEM BY WASHING DISHES AND LAUNDRY IN LARGE LOADS. SPREAD LOADS OVER THE WEEK RATHER THAN DOING ALL LAUNDRY ON A SINGLE DAY.
 - PROHIBIT VEHICULAR TRAFFIC AND HOOFED ANIMALS FROM THE SEPTIC SYSTEM AREA.
- PUMP:**
THE PUMP SHALL BE OF THE SIZE AND TYPE INDICATED ON THE PLANS AND SHALL INCLUDE THE FOLLOWING:
1) A HANDS OFF AUTO (HOA) SWITCH.
2) AN AUDIO AND VISIBLE ALARM AND NECESSARY EFFLUENT SENSING DEVICE TO INDICATE A HIGH WATER CONDITION.
3) USE EITHER PILL OR MERCURY TYPE FLOAT SWITCH.
4) SET PUMPING VOLUME AS STATED IN THE PUMP REQUIREMENTS.
5) PUMP TO BE SET A MINIMUM OF 8 INCHES FROM THE BOTTOM OF THE SUMP.
- SUMP:**
1) THE SUMP SHALL HAVE A WORKING CAPACITY OF 1.0 TIMES THE DESIGN FLOW DESIGNATED. THE CAPACITY SHALL INCLUDE THE DOSE VOLUME AND 24-HOUR STORAGE VOLUME.
2) ACCESS TO BE PROVIDED BY A MINIMUM 24-INCH DIAMETER WATERPROOF AIR TIGHT RISER AND LID SYSTEM.
3) ALL PIPE AND OR ELECTRICAL CONNECTIONS MADE THROUGH THE RISER EITHER TO BE PRECAST INTO THE RISER OR SEALED WITH GASTIGHT COMPRESSION CONNECTORS.


ELECTRICAL FEATURES
THE FOLLOWING ELECTRICAL FEATURES TO BE PROVIDED
1) AN OUTDOOR TYPE CONTROL BOX CONTAINING A FUSED DISCONNECT AND MOTOR PROTECTION SWITCH. SEE THE PUMP REQUIREMENT SECTION OF THE PLANS FOR THE MODEL NUMBER AND REQUIREMENTS.
2) THE CONTROL BOX TO BE MOUNTED ON THE BUILDING BEING SERVED IF WITHIN 20 FEET OF THE SUMP OTHERWISE INSTALL ON A 4"x4" POST THAT IS INSTALLED SECURELY. CONTROL PANEL TO BE VISIBLE FROM THE ROADWAY IF AT ALL POSSIBLE.
3) ALARM AND PUMP TO BE INSTALLED ON SEPARATE CIRCUITS THAT ARE OF SIZE LARGE ENOUGH FOR THE RESPECTIVE USES.
4) ELECTRICAL CONDUIT SHALL BE PVC AND SEPARATE CONDUITS SHALL BE PROVIDED TO POWER PUMP AND FLOATS.

PRESSURE PIPING
1) THE PIPE FROM THE SUMP TO THE DRAINFIELD SHALL BE PVC IN THE SIZE AND SCHEDULE SPECIFIED ON THE PLANS.
2) A UNION SWING CHECK VALVE AND DOUBLE WEDGE GATE VALVE SHALL BE INSTALLED IN THE SUMP CHAMBER IN THIS ORDER AWAY FROM THE PUMP. ALTERNATIVELY THESE ITEMS CAN BE INSTALLED IN A VALVE BOX NEXT TO THE SUMP CHAMBER.
3) CONCRETE THRUST BLOCKS SHALL BE INSTALLED WHEN CHANGE IN PIPE DIRECTION IS 45 DEGREES OR GREATER.

PERMITS
ASIDE FROM THE INDIVIDUAL SEWAGE DISPOSAL SYSTEM PERMIT ADDITIONAL PERMIT (S) WILL BE REQUIRED BY THE BUILDING INSPECTION DEPARTMENT FOR PUMP INSTALLATION.



DIVERSION VALVE BOX DETAIL
NOT TO SCALE



TYP. LEACHLINE INSPECTION WELL
NOT TO SCALE

DETAILS

Revisions:

PREPARED FOR:
Brian Johnson
PO Box 1139
Homewood, CA 96141

RAISED BED/SAND FILTER SYSTEM
21 CALLE DEL ONDA
Stinson Beach, CA
APN 195-162-49

AYS Engineering Group, Inc
PO Box 5693, Petaluma, CA 94955
Voice (707) 763-6620, Fax (707) 781-8061

Job No. 2018-038
Date 11-19-18
Drawn By: tkp
Checked By: tkp
Scale as shown

Sheet 2 of 2

REGISTERED CIVIL ENGINEER
TROY K. PEARCE
STATE OF CALIFORNIA
17878

2