227 REED STREET

MILL VALLEY, CA 94941 APN# 048-101-26

DESIGN REVIEW SUBMITTAL: 1.5.2025

GENERAL NOTES

1. VERIFY ALL EXISTING DIMENSIONS & CONDITIONS AT THE SITE & NOTIFY ARCHITECT OF ANY VARIATIONS OR CONFLICTING OR MISSING DIMENSIONS OR DATA PRIOR TO BIDDING OR COMMENCING WORK. USE WRITTEN DIMENSIONS ONLY; DO NOT SCALE DRAWINGS FOR THE PURPOSE OF DETERMINING A DIMENSION DURING CONSTRUCTION.

2. CONDITIONS NOT SPECIFICALLY DETAILED SHALL BE BUILT TO CONFORM TO SIMILAR CONSTRUCTION, IN ACCORDANCE WITH THE BEST COMMON PRACTICE AND/OR MANUFACTURER'S SPECIFICATIONS FOR THE INSTALLATION OF THEIR MATERIALS OR ITEMS.

3. ALL MATERIALS, WORKMANSHIP & METHODS SHALL CONFORM TO CURRENTLY ADOPTED CALIFORNIA BUILDING CODE (CBC), CALIFORNIA PLUMBING CODE (CPC), CALIFORNIA MECHANICAL CODE (CMC), AND THE CALIFORNIA ELECTRICAL CODE (CEC) AND ANY OTHER APPLICABLE CODES & ORDINANCES OF THE LOCAL JURISDICTION.

4. SAFETY: THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR SAFETY ON THE JOB SITE AND ADHERE TO ALL FEDERAL, STATE LOCAL AND O.S.H.A. SAFETY REGULATIONS.

5. CONSTRUCTION BRACING & SHORING: THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL BRACING AND SHORING REQUIRED DURING CONSTRUCTION UNTIL ALL CONSTRUCTION IS COMPLETE.

6. DO NOT STORE CONSTRUCTION MATERIALS OR OPERATE CONSTRUCTION EQUIPMENT IN SUCH A MANNER THAT DESIGN LIVE LOADS OF THE STRUCTURES ARE EXCEEDED. DO NOT STORE CONSTRUCTION MATERIALS ON OVERHANGING FRAMING.

7. TREES LOCATED CLOSE TO THE CONSTRUCTION SITE SHALL BE PROTECTED FROM INADVERTENT DAMAGE FROM CONSTRUCTION EQUIPMENT BY WRAPPING TRUNKS WITH PROTECTIVE MATERIALS, AVOIDING FILL OF ANY TYPE AGAINST THE BASE OF THE TRUNKS AND AVOIDING AN INCREASE IN SOIL DEPTH AT THE FEEDING ZONE OR DRIP LINE OF THE RETAINED TREES.

8. [IF APPLICABLE:] SHOWERS AND TUB SHALL USE INDIVIDUAL CONTROL VALVES OF THE PRESSURE BALANCE OR THE THERMOSTATIC MIXING VALVE TYPE. (CPC 420).

9. [IF APPLICABLE:] GLAZING USED IN DOORS AND PANELS OF SHOWER AND TUB ENCLOSURES SHALL BE FULLY TEMPERED GLASS, LAMINATED SAFETY GLASS OR APPORVED PLASTIC OF A SHATTER-RESISTANT TYPE. (CBC 5406 (D) 5)

10. [IF APPLICABLE:] SHOWER WALLS SHALL BE FINISHED WITH A NON-ABSORBENT SURFACE TO A HEIGHT OF 72" OR GREATER ABOVE DRAIN

11. INSTALL CERTIFIED INSULATION MATERIALS PER THE TITLE 24 MANDATORY MEASURES CHECKLIST MF-1R AND TITLE 24 ENERGY REPORT (ATTACHED ONLY IF APPLICABLE). INSULATION INSTALLED SHALL MEET FLAME SPREAD & SMOKE DENSITY REQUIREMENTS OF STATE OF CALIFORNIA TITLE 24, CALIFORNIA ELECTRICAL CODE, CALIFORNIA CODE OF REGULATIONS.

SYMBOL LEGEND

ROOM NAME	STUDIO A room name 117 room number
WALL TYPE	- —99A
DOOR NUMBER	(101)
WINDOW NUMBER	9>
RCP ELEVATION	+9'-6"
FINISH FLOOR ELEVATION	(₹'-XX''

EL. = +X'-X" A.F.F. - elevation view direction ___sheet number — drawing number

FIRST FLR FFE ___ - datum location

x drawing number -sheet number — view direction

ELEVATION -sheet number -drawing number — drawing number elevation designation INTERIOR ELEVATION - sheet number

COLUMN GRIDLINE ADDENDUM

EXISTING WALLS TO REMAIN EXISTING WALLS TO BE REMOVED EXISTING ELEMENTS TO BE REMOVED NEW TYP. NON-RATED WALL

1-HOUR RATED WALL: 1 LAYER TYPE X 5/8" GWB EACH SIDE CENTER LINE

LINE OF ITEM ABOVE


ABBREVIATIONS

A.D. A.S.F.	AREA DRAIN ABOVE SUB FLOOR	GA GALV	GUAGE GALVANIZED	RD REF	ROOF DRAIN REFERENCE
ADJ	ADJUSTABLE	GFCI	GROUND FAULT CIRCUIT INTERRUPTER	REFR	REFRIGERATOR
AFF	ABOVE FINISH FLOOR	GL	GLASS	REG	REGISTER
ALUM	ALUMINUM	GND	GROUND	REINF	REINFORCED
ARCH	ARCHITECTURAL	GWB	GYPSUM WALLBOARD (SHEETROCK)	REQ'D	REQUIRED
ATTN	ATTENTION	H.B.	HOSE BIB	RET	RETURN
BKSHLF	BOOKSHELF	HDWR	HARDWARE	REV	REVISED
BLKG	BLOCKING	HDR	HEADER	RM	ROOM
BLDG	BUILDING	HP	HIGH POINT	R.O.W.	RIGHT OF WAY
BD	BOARD	HORIZ	HORIZONTAL	RWL	RAIN WATER LEADER
BTWN	BETWEEN	HT	HEIGHT	S.A.D.	SEE ARCHITECTURE DRAWINGS
B.O.	BY OWNER	ID	INSIDE DIMENSION	SCHED	SCHEDULE
CAB		IN	INCH	SHTG	SHEATHING
	CABINETRY CENTERLINE			SIM	SIMILAR
CL		INSUL INT	INSULATION	SPEC	
CLO CLG	CLOSET		INTERIOR		SPECIFICATION
	CEILING	JB	JUNCTION BOX	SQ	SQUARE
CMU	CONCRETE MASONRY UNIT	JT	JOINT	SF	SQUARE FEET
COL	COLUMN	LAM	LAMINATED	S.M.D.	SEE MECHANICAL DRAWINGS
CONC	CONCRETE	LAV	LAVATORY	S.S.D.	SEE STRUCTURAL DRAWINGS
CONT	CONTINUOUS	LP	LOW POINT	SS	STAINLESS STEEL
CP	CENTER POINT	LT	LIGHT	STD	STANDARD
C.T.	CERAMIC TILE	MECH	MECHANICAL	STL	STEEL
DIA	DIAMETER	MIN	MINIMUM	STRUCT	STRUCTURAL
DBL	DOUBLE	MR	MOISTURE RESISTANT	SUSP	SUSPENDED
DET	DETAIL	MTL	METAL	T	TREAD
DN	DOWN	(N)	NEW	TBD	TO BE DETERMINED
DEPT	DEPARTMENT	N.I.C.	NOT IN CONTRACT	TEMP	TEMPERED
DW	DISHWASHER	NOM	NOMINAL	T.T.	TOP OF
DWG	DRAWINGS	NTS	NOT TO SCALE	T.T.P.	TOP OF PLATE
DWR	DRAWER	OC	ON CENTER	T.T.C.	TOP OF CONCRETE
EA	EACH	OD	OUTSIDE DIMENSION	T.T.W.	TOP OF WALL
EJ	EXPANSION JOINT	OH	OVERHEAD	THK	THICK
ELEC	ELECTRICAL	OPN'G	OPENING	TYP	TYPICAL
ELEV	ELEVATION	OPP	OPPOSITE	UON	UNLESS OTHERWISE NOTED
EQ	EQUAL	PL	PROPERTY LINE	UNF	UNFINISHED
(E)	EXISTING	PLAS	PLASTER	VAR	VARIES
EXT	EXTERIOR	PLYWD	PLYWOOD	VCT	VINYL COMPOSITE TILE
F.O.F.	FACE OF FINISH	PT	POINT	VEST	VESTIBULE
F.O.S.	FACE OF STRUCTURE	PTD	PAINTED	VIF	VERIFY IN FIELD
FAU	FORCED AIR UNIT	QTY	QUANTITY	W.C.	WATER CLOSET
FIN	FINISH	R	RISER	WD	WOOD
FLR	FLOOR	RAD	RADIUS	W.R.	WATER RESISTANT
F.R.	FIRE RATED	RCP	REFLECTED CEILING PLAN	WT	WEIGHT


FRONT FACADE



VICINITY MAP



ZONING MAP



PROJECT SITE

APPLICABLE CODES

2022 CALIFORNIA RESIDENTIAL CODE

ALL CONSTRUCTION, REGARDLESS OF DETAILS ON PLANS, SHALL COMPLY WITH THE FOLLOWING CODES: CURRENT MILL VALLEY MUNICIPAL CODE, 2022 CALIFORNIA BUILDING CODE (CBC)

2022 CALIFORNIA ELECTRICAL CODE (CEC) 2022 CALIFORNIA MECHANICAL CODE (CMC) 2022 CALIFORNIA PLUMBING CODE(CPC) 2022 CALIFORNIA BUILDING ENERGY STANDARDS 2022 CALIFORNIA GREEN BUILDING STANDARDS CODE

PROJECT DIRECTORY

KATIE & JOE RAFFETO 227 REED STREET MILL VALLEY, CA 94941 415.310.0821 JOERAFFETTO@HOTMAIL.COM

KATIE@KATIERAFFETTO.COM

BROOKS MCDONALD ARCHITECTURE 1615 BRIDGEWAY SAUSALITO, CA 94965 415.350.8011 BROOKS@BROOKSMCDARCHITECTURE.COM CONTACT: KELLY TURBIN CONTACT: BROOKS MCDONALD

STRUCTURAL ENGINEER: TURBIN STRUCTURAL ENGINEERS 244 MILLER AVE, MILL VALLEY, CA 94941 415.373.9472 x 105 KELLY@TURBINSTRUCTURAL.COM

GENERAL CONTRACTOR:

EXCAVATION/LOT COVERAGE

EXCAVATION CHART (CUBIC YARDS)

LOCATION	CUT	FILL
GARAGE & PARKING	0	0
RESIDENCE (FOUNDATIONS)	13	0
RESIDENCE (BENEATH DECK)	0	13
LANDSCAPE	0	0
TOTAL	0	
TOTAL	U	U
TOTAL OFF-HAUL = 0 CU YARDS		

LOT COVERAGES

E01 00 1 E10 10 E	
LOT SIZE*:	88,862 SF
EXISTING LOT COVERAC	GES: (8%)
IMPERVIOUS:	6,975 SF
PERVIOUS:	81,887 SF
PROPOSED LOT COVER	AGES: (8%)
IMPERVIOUS:	7,428 SF
PERVIOUS:	81434 SF

AREA OF WORK SCOPE

((\L) (\O)	,, O.K.
1ST FLOOR	827
2ND FLOOR	961
TOTAL	1788 SF

% OF (E) FLOOR AREA 57%

(E) FLOOR AREA

PROJECT DESCRIPTION

APPLICANT REQUESTS DESIGN REVIEW APPROVAL FOR A HORIZONTAL AND VERTICAL ADDITION TO THE NORTH SIDE OF THE BUILDING, INTERIOR REMODEL AND NEW DECK ALONG THE WEST SIDE OF THE BUILDING.

DESIGN REVIEW APPROVAL IS REQUIRED BECAUSE THE PROJECT WOULD INVOLVE AN ADDITION THAT IS <3000 SF FOR A 2-STORY ADDITION.

PROJECT DATA

PARCEL INFORMATION

ZONING DISTRICT:

COMMUNITY PLAN:

SIDE SETBACKS:

W.U.I. SLOPE

048-101-26 PROPERTY ADDRESS: 227 REED ST, MILL VALLEY, CA 94941 LOT AREA: 88,862 SF (ASSESSOR) FLOOD ZONE:

ZONING INFORMATION R1 - RESIDENTIAL SINGLE FAMILY PLANNING DISTRICT: DISTRICT 4 TAMALPAIS 30% (26,658 SF)

FRONT & REAR SETBACK: MAX F.A.R.: MAX HEIGHT: 30' MAIN BUILDING 47%

BUILDING INFORMATION OCCUPANCY NO. STORIES: CONSTRUCTION TYPE: SPRINKLERS: FLOOR AREA: MAX ADDITIONAL SF: TOTAL ALLOWABLE SF: LOT COVERAGE:

R-3 SINGLE FAMILY RESIDENTIAL 2 EXISTING / 2 PROPOSED

SPRINKLERED ON SEPARATE PERMIT PER NFPA 13D 3315 SF EXISTING, 3664 SF PROPOSED FLOOR AREA (3315) X 30% = 995 SF MAX 30% F.A.R. = 88,862 X .30 = 26,658.6 SF 40% MAX (35,544.8)

FLOOR AREA CALCS (SQUARE FEET) MCC 22.130.030

FLOOR	EXISTING	PROPOSED	DELTA
1ST FLOOR	2180	2339	+159
2ND FLOOR	1135	1325	+190
TOTAL FLOOR AREA	3315	3664	+349
FAR	3.7%	4.1%	
CARPORT	479	479	EXEMF

BUILDING AREA CALCS (SQUARE FEET) MCC 22.130.030

FLOOR	EXISTING	PROPOSED	DELTA
HOUSE FLOOR AREA	3315	3664	+349
CARPORT	479	479	+0
TOTAL BLDG AREA	3794	4143	+349

2022 CAL GREEN MANDATORY MEASURES

- STORM WATER TO BE MANAGED DURING CONSTRUCTION PER CALGREEN SECTION 4.106.2. SURFACE WATER TO BE KEPT AWAY FROM BUILDINGS PER CALGREEN SECTION 4.106.3
- ELECTRIC VEHICLE SUPPLY EQUIPMENT (EVSE) SHALL BE INSTALLED. BEST MANAGEMENT WORK SHEET FOR CONSTRUCTION WASTE MANAGEMENT TO BE SUBMITTED BY CONTRACTOR. 5. DUCT SYSTEMS ARE TO BE SIZED, DESIGNED, AND EQUIPMENT IS SELECTED PER SECTION 4.507.2. HVAC SYSTEM INSTALLERS ARE TO BE TRAINED AND CERTIFIED AND SPECIAL INSPECTORS EMPLOYED BY THE ENFORCING AGENCY TO BE QUALIFIED. AUTOMATIC IRRIGATION SYSTEM CONTROLLERS INSTALLED AT THE TIME OF FINAL INSPECTION SHALL BE WEATHER-BASED
- 7. INSTALL ONLY A DIRECT-VENT SEALED-COMBUSTION GAS OR SEALED WOOD-BURNING FIREPLACE, OR A SEALED WOODSTOVE
- MEETING EPA NEW SOURCE PERFORMANCE STANDARDS (NSPS) EMISSION LIMITS AND MILL VALLEY WOOD. 8. DUCT OPENINGS AND OTHER RELATED AIR DISTRIBUTION COMPONENT OPENINGS SHALL BE COVERED DURING CONSTRUCTION. BURNING APPLIANCES ORDINANCE.
- ADHESIVES, SEALANTS AND CAULKS SHALL BE COMPLIANT WITH VOC AND OTHER TOXIC COMPOUND LIMITS. 10. PAINTS, STAINS AND OTHER COATINGS SHALL BE COMPLIANT WITH VOC LIMITS.
- 11. AEROSOL PAINTS AND OTHER COATINGS SHALL BE COMPLIANT WITH PRODUCT WEIGHTED MIR LIMITS FOR ROC AND OTHER TOXIC COMPOUNDS.
- 12. DOCUMENTATION SHALL BE PROVIDED TO VERIFY THAT COMPLIANT VOC LIMIT FINISH MATERIALS HAVE BEEN USED. 13. CARPET AND CARPET SYSTEMS SHALL BE COMPLIANT WITH VOC LIMITS.
- 14. PARTICLEBOARD, MEDIUM DENSITY FIBERBOARD (MDF), AND HARDWOOD PLYWOOD USED IN INTERIOR FINISH SYSTEMS SHALL COMPLY WITH LOW FORMALDEHYDE EMISSION STANDARDS. 15. VAPOR RETARDER AND CAPILLARY BREAK IS INSTALLED AT SLAB ON GRADE FOUNDATIONS.
- 16. MOISTURE CONTENT OF BUILDING MATERIALS USED IN WALL AND FLOOR FRAMING IS CHECKED BEFORE ENCLOSURE. 17. EACH BATHROOM (WITH TUB OR SHOWER) MUST BE MECHANICALLY VENTILATED WITH A HUMIDITY CONTROLLED ENERGY STAR
- COMPLIANT EXHAUST FAN WHICH TERMINATES OUTSIDE OF THE BUILDING UNLESS OTHERWISE A COMPONENT OF A WHOLE HOUSE VENTILATION SYSTEM. 18. DUCT SYSTEMS ARE SIZED AND DESIGNED AND EQUIPMENT IS SELECTED USING THE FOLLOWING METHODS:
- 18.1. ESTABLISH HEAT LOSS AND HEAT GAIN VALUES ACCORDING TO ANSI/ACCA MANUAL J-2004 OR EQUIVALENT.
- 18.2. SIZE DUCT SYSTEMS ACCORDING TO ANSI/ACCA 1 MANUAL D -2009 OR EQUIVALENT.
- 18.3. SELECT HEATING AND COOLING EQUIPMENT ACCORDING TO ANSI/ACCA 3 MANUAL S-2004 OR EQUIVALENT. 19. ANNULAR SPACES AROUND PIPES, ELECTRIC CABLES, CONDUITS, OR OTHER OPENINGS IN PLATES AT EXTERIOR WALLS SHALL BE PROTECTED AGAINST THE PASSAGE OF RODENTS BY CLOSING SUCH OPENINGS WITH CEMENT MORTAR, CONCRETE MASONRY OR SIMILAR METHOD ACCEPTABLE TO THE ENFORCING AGENCY.
- 20. RECYCLE AND/OR SALVAGE FOR REUSE A MINIMUM OF 65 PERCENT OF THE NONHAZARDOUS CONSTRUCTION AND DEMOLITION WASTE BY UTILIZING A WASTE MANAGEMENT COMPANY, PER SECTION 4.408.3.
- 21. AN OPERATION AND MAINTENANCE MANUAL SHALL BE PROVIDED TO THE BUILDING OCCUPANT OR OWNER.

SHEET INDEX

- ARCHITECTURAL DRAWINGS
- A0.1 PROJECT INFORMATION
- A0.2 BMP'S, STORMWATER MANAGEMENT PRACTICES A1.0 EXISTING SITE & ROOF PLAN
- A1.01 EXISTING SITE & ROOF PLAN AT 1:20 SCALE
- A1.1 PROPOSED SITE & ROOF PLAN
- A1.11 PROPOSED SITE & ROOF PLAN AT 1:20 SCALE
- A1.2 GRADING, DRAINAGE, & UTILITIES PLAN A1.3 STORMWATER CONTROL PLAN & CONSTRUCTION MANAGEMENT
- A1.4 CONCEPTUAL LANDSCAPE PLAN A1.5 STORY POLE PLAN
- A2.0 EXISTING FIRST FLOOR FLOOR PLAN
- A2.1 PROPOSED FIRST FLOOR FLOOR PLAN A2.2 EXISTING SECOND FLOOR PLAN
- A2.3 PROPOSED SECOND FLOOR PLAN
- A4.0 EXISTING & PROPOSED NORTH EXTERIOR ELEVATIONS
- A4.1 EXISTING & PROPOSED EAST EXTERIOR ELEVATIONS
- A4.2 EXISTING & PROPOSED WEST EXTERIOR ELEVATIONS
- A5.0 EXISTING & PROPOSED BUILDING SECTIONS
- A5.1 MATERIALS BOARD & SCHEDULE
- SURVEY

 $\mathbf{Z} \stackrel{ ext{T}}{\circ}$


OA

 \mathbf{B}

9 4 A

ESIDIY CA

ш



1.8.2024

DR REV2:

A0.1

PROJECT INFO

CONSTRUCTION EROSION CONTROL PLAN

Install erosion control measures conforming to the EROSION CONTROL STANDARDS and as shown on the drawings and described in the following notes. Install all erosion control measures before October 15th.

LIMITS ON THE WORK AREA

- I. Phase grading work to minimize the extent of the disturbed area prior to restoration.
- 2. Confine grading within the construction limits shown on the drawings. Mark the construction limits using temporary fencing or flagging.
- 3. Do not disturb vegetation outside the construction limits.

EXCAVATED MATERIAL

I. Use excavated material to construct finished grades as shown on the drawings and in accordance with the geotechnical specifications for the project.

Supply Water to Wash

2. Remove excess excavated material from the site and dispose in approved off-site disposal areas.

3. Avoid tracking soil onto streets. Install a temporary stabilized construction entrance in accordance with TC-1 BMP Handbook and Standard Erosion Control Measure A (ABAG, 1995).

TEMPORARY SOIL STOCKPILES

I. Place excavated top soil from the drilled piers, foundation wall excavation and retaining wall excavation in one or more stockpiles located as shown on the drawings. Grade temporary soil stockpiles to a maximum height of five feet, with maximum side slope of 2H:IV. Avoid creating depressions that trap water.

2. Install silt fence or straw wattle around each soil stockpile in accordance with the manufacturer's recommendations. Brace the silt fence sufficiently to support the

weight of any sediment that accumulates against it.

DIVERSION BERMS AND DOWN-SLOPE PIPES

I. Construct earth diversion berms at the top of cut and fill slopes to intercept runoff and divert it around the disturbed area.

2. Install pipes (HDPE, PVC or corrugated metal) to convey water down steep

3. Wherever possible, construct berms at near level gradients to reduce flow

velocities and the possibility of erosion damage. 4. Comply with EC-10 and EC-11 BMP Handbook and Standard Erosion Control

Measure E for diversion berms and Measure G for down-slope pipes (ABAG,

TEMPORARY PIPES AND LINED DITCHES

I. Install temporary pipes and construct lined ditches to convey runoff to the temporary sediment basin.

2. Line ditches with rock, erosion control blankets or concrete, depending on the flow velocity and slope of the ditch.

3. Where ditches cannot be used, install HDPE, PVC or corrugated metal pipe.

4. Size all temporary pipes and ditches for the 10-year, 1-hour storm intensity of 3.0 inches per hour.

5. Erosion Control Blanket Lining (velocity less than 6 fps): Long-term coconut fiber erosion control blanket with organic jute fiber netting top and bottom. CI25BN manufactured by North American Green. Install using rigid 6 inch-long biodegradable BioSTAKEs by North American Green.

6. Rock Lining (velocity greater than 6 fps and less than 8 fps): Caltrans No.1 rock slope protection placed in a twelve- inch-thick layer over a nonwoven 4 oz/sy geotextile.

7. Comply with EC-12 BMP Handbook and Standard Erosion Control Measures F and I (ABAG, 1995).


TEMPORARY SEDIMENT BASIN

I. When directed by the Engineer during construction, construct a temporary sediment basin to detain runoff and allow suspended sediment to settle out of surface water runoff before it is discharged to the existing stormwater drainage system on the site. Discharge of surface water runoff from disturbed areas directly to the stormwater drainage system is not allowed. Filter all surface runoff through straw wattle or silt fence.

2. Maintain the sediment basin throughout construction until the disturbed area is revegetated and slopes are stabilized.

3. Remove accumulated sediment from the sediment basin before the volume reaches 25% of the total basin volume. Inspect the basin after every significant rainfall and, if necessary, remove the accumulated sediment.

4. Comply with SE-2, BMP Handbook and Standard Erosion Control Measures O and P, (ABAG, 1995).



SEDIMENT FILTER

I. Install sediment filters at all stormwater drainage inlets and culvert inlets.

2. Comply with SE-10 BMP Handbook and Standard Erosion Control Measures M and N, (ABAG, 1995).

SLOPE PROTECTION

I. Install an erosion control blanket in accordance with manufacturer's recommendations on all disturbed areas with a slope equal to or steeper than 3H:IV. (EC-7, BMP Handbook)

2. Install straw wattles along the contour of the slope at 20 feet on center and as shown on the drawings. Anchor using I'xI"xI&"wood stakes at 4 feet on center. (SE-5, BMP Handbook)

3. Erosion Control Blanket: Long-term coconut fiber erosion control blanket with organic jute fiber netting top and bottom. CI25BN manufactured by North American Green. Install using riqid 6 inch-long biodegradable BioSTAKEs by North American

4. RiceStraw Wattle, 8.5-inch diameter, with biodearadable netting. Anchor using 34" × 34" wood stakes at 4 ft spacing.

SILT FENCE

SECTION A - A under rocks

The entrance shall be maintained to prevent sediment tracking flowing onto public right-of-ways. This may require top dressing

When necessary, wheels shall be cleaned prior to entering public

When washing is required, it shall be done on an area stabilized

with crusned stone that drains into an approved sediment trap o sediment basin. Rumple plates or tire wash can be added.

Site Entrance

repair and/or cleanout or other measures that trap sediment.

— Min 50° (15m).

12" min

I. Install prefabricated silt fence at the locations shown on the drawings and at other fieldidentified locations where needed to trap eroded sediment and

reduce runoff velocities during construction.

2. Silt Fence: Prefabricated silt fence consisting of a woven, uv-stabilized geotextile with sewn pockets for wooden stakes. Mirafi prefabricated Silt Fence (100X) with 10 foot post spacing. Install bottom of fabric in excavated toe trench in accordance with Manufacturer's recommendations.

Extra strength filter fabric needed without wire mesh support


TEMPORARY CHECK DAMS

1. Construct temporary rock check dams in the larger drainage ditches to reduce velocities and control erosion. Use rock sized to resist the estimated flow velocity. Locate check dams between 10 and 50 feet apart, depending on the slope of the ditch.

2. Comply with SE-4 BMP Handbook and Standard Erosion Control Measure H, (ABAG, 1995).

SITE RESTORATION PLAN

I. Restore all disturbed areas of the site after completing construction of the project.



Erosion Blanket

Note: Actual layout determined in the field

2. Remove temporary erosion control measures installed during construction.

3. Grade the site to eliminate depressions where stormwater runoff could accumulate or where runoff could flow in a concentrated channel. Grade the site to slope toward the permanent stormwater collection system inlets where appropriate.

4. Apply mulch and native grass seed to disturbed areas in accordance with the requirements for materials, seed mixes and application methods detailed in the project landscaping specification.

5. Install erosion control blanket and turf reinforcing material as detailed on the plans.

6. Install rip rap erosion protection as detailed on the plans

EROSION CONTROL STANDARDS

I. Install all erosion control measures in accordance with the details and methods specified in the "Manual of Standards for Erosion & Sediment Control Measures", Second Edition, May 1995, Association of Bay Area Governments (ABAG). Available online at http://store.abaq.ca.gov/environment.asp

2. Comply with all rules, regulations and procedures of the National Pollution Discharge Elimination System (NPDES) for construction activities as required by the California Regional Water Quality Control Board and City of Lafayette. Comply with all requirements of the Project Erosion Control

3. Install erosion control measures in accordance with the product manufacturer's recommendations, the California Stormwater Best Management Practices Handbook (California Stormwater Quality Association, www.cabmphandbooks.com) and the Project Erosion Control

STORMWATER POLLUTION PREVENTION PLAN

<u>PAINTING</u>

- I. Do not rinse paint brushes or materials into a stormwater drain inlet or onto the
- 2. Paint out excess water-based paint before rinsing brushes, rollers or containers in a sink. If a sink is not available, direct wash water to a soil area and spade it into the soil with a shovel.
- 3. Paint out excess oil-based paint before cleaning brushes in paint thinner.
- 4. Whenever possible, filter paint thinner and solvents for reuse. Dispose of oilbased paint sludge and unusable thinner as hazardous waste.
- 5. Dispose of empty paint cans as hazardous waste.
- 6. Dispose of paint chips and dust from non-hazardous dry stripping of paints as trash. Dispose of paint chips and dust containing lead or tributyl tin as hazardous

PAVING AND ASPHALT WORK


I. Do not pave during wet weather or when rain is forecast.

- 2. Always cover stormwater drain inlets and manholes when paving or applying seal coat, tack coat, slurry seal or fog seal.
- 3. Prevent paving materials from entering stormwater drain inlets, ditches and stream
- 4. Do not use water to wash down fresh asphalt or concrete pavement.
- 5. Do not sweep or wash down excess materials into stormwater drain inlets, ditches or stream channels. Collect excess materials and return them to stockpiles or dispose of them as trash.


MATERIAL STORAGE AND WASTE DISPOSAL

- I. Sweep streets and other paved areas daily. Never wash down streets or work
- 2. Store stockpiles of dirt, sand, asphalt, concrete, grout and mortar under cover and away from drainage areas. Do not allow these materials to reach stormwater drain inlets, ditches or stream channels.

3. Wash out concrete equipment, concrete trucks and concrete pumps at a designated on-site area for washing where water and excess concrete will flow into a temporary pit in a dirt area. Let water seep into the soil and dispose of hardened concrete with trash.



it will not run into a gutter, street or stormwater drain inlet.



DEWATERING OPERATIONS

- I. Reuse water for dust control, irrigation or another on-site purpose to greatest extent possible.
- 2. Contact the local Stormwater Coordinator before discharging water to a street, stormwater drain or creek. Filtration or diversion through a basin, tank or sediment trap may be required.

VEHICLE AND EQUIPMENT MAINTENANCE

- I. Frequently inspect vehicles and equipment for leaks. Use drip pans to catch leaks until repairs are made. Promptly repair leaks.
- 2. Fuel and maintain vehicles on-site only in a bermed area or over a drip pan that is big enough to prevent runoff.
- 3. Clean vehicles or equipment using clean water in a bermed area that will not allow rinse water to run into streets, stormwater drain inlets, ditches or stream channels.
- 4. Do not clean vehicles on-site using soap, solvents, degreasers or steam cleaning equipment.

SAW CUTTING

- I. Completely cover or barricade stormwater drain inlets when saw cutting. Use filter fabric, sand bags or fine gravel dams to keep slurry out of the stormwater drain
- 2. Shovel, absorb or vacuum saw-cut slurry and pick up all waste as soon as work is finished on one location or at the end of the work day.
- 3. Immediately cleanup and remove any saw-cut slurry that enters a stormwater drain


HAZARDOUS MATERIAL MANAGEMENT

- I. Label all hazardous materials and hazardous wastes such as pesticides, paint, thinner, solvents, fuel, oil and antifreeze in accordance with City, State and Federal requlations.
- 2. Store hazardous materials and wastes in secondary containment and cover them
- 3. Follow manufacturer's application instructions for hazardous materials and do not use more than necessary. Do no apply chemicals outdoors when rain is forecast within 24 hours.

EROSION CONTROL MONITORING AND MAINTENANCE

Monitor erosion control measures and disturbed areas of the site between October 15th and April 1st. Apply corrective measures as needed to maintain sediment control. Inspect erosion control measures weekly, prior to forecast rain storms, daily during extended rainfall and after the conclusion of every significant storm. Take appropriate corrective action as described in the following check list. Repair Areas where erosion is evident and reapply BMPs as soon as possible. Care should be exercised to minimize the damage to protected areas while making repairs, as any area damaged will require reapplication of BMPs. If washout or breakage occurs, re-install the material after repairing the damage to the slope or channel.

	CONTROL MEASURE	<u>Inspection Items</u>	ACTION TO BE TAKEN
Veg	 Rill or gullies forming Bare soil patches Sediment at toe of slope 		 Repair top-of-slope diversion swales Construct additional diversion swales if necessary Fill and regrade eroded areas Reseed, fertilize and mulch bare areas
Swales		 Low spots in swale Sediment or debris in the channel Erosion of unlined channel surface Erosion of channel lining 	 Repair breaches Fill low spots with compacted soil Remove obstructions
Pipe	drains	 Blocked inlet or outlet Runoff bypassing inlet Erosion at outlet 	 Remove sediment and debris Enlarge inlet headwall Enlarge riprap apron or use larger rock
Gras	ssed waterways	Bare areas Channel capacity reduced by tall growth	 Reseed, mulch and install netting Divert flow, if possible, until grass is established Mow grass
1 '	ap-lined erways	Scour beneath rockDislodged rock	 Install filter fabric beneath rock and make sure edges of fabric are anchored into the subsoil Replace rock or add larger rock
Outle prote		 Erosion below outlet Outlet erosion Dislodged rock 	 Replace rock or add larger rock Enlarge riprap apron Add erosion protection to the channel downstream from the outlet Install filter fabric beneath rock and make sure edges of fabric are anchored into the subsoil
Sedi trap		 Sediment level near outlet elevation Obstructed outlet Basin not dewatering between storms Damaged embankment Spillway erosion Outlet erosion Sediment storage zone fills to quickly 	 Remove sediment Remove debris from outlet trash rack Clear obstruction and sediment away from the outlet structure Rebuild damaged embankments Add rock and filter fabric to the spillway channel Enlarge or repair riprap apron at the outlet structure Increase the depth of the basin or divert runoff to a different sediment basin
Stra	w Wattles	 Undercutting of straw wattle Damaged wattle Runoff escaping around end of wattle Sediment level near top of wattle 	 Fill undercut area with soil and compact, re-anchor the wattle with wooden stakes Replace damaged wattles Extend wattle Remove sediment or install additional wattles upslope
Silt i	Fences	 Undercutting of silt fence Fence collapsing Torn fabric Runoff escaping around fence Sediment level near top of the fence 	 Anchor bottom of silt fence in a trench filled with compacted backfill Replace fence posts or install additional posts Replace torn fabric Extend fence Remove sediment before it reaches half the fence height
Chec	ck Dams	 Sediment accumulation Flow escaping around the sides of check dam Displacement of timber, sandbags or rock 	 Remove sediment after each storm Build up the ends of the check dam and provide a low center area for overflow Reinforce the check dam with larger rock or divert a portion of the runoff to another outlet
Inlet	Structures	 Flooding around or below inlet Undercutting of silt fence 	 Remove accumulated sediment See recommended actions for silt fencing



- (I) Check with your local Planning and Public Works departments for <u>creek setback</u> requirements. Grading and/or building may be limited within creekside buffers.
- (2) During grading phase, track-walk up and down slopes (not parallel to them).
- (3) <u>Stabilize site entrance</u> and temporary driveway use 3" crushed rock for minimum of 50' (or as far as possible) to prevent tracking soil offsite. This can be used in conjunction with a tire wash or rumble plates.

- (4) Use <u>straw wattles</u> (see Slope Protection Notes).
- (5) Install <u>silt fence</u> along contours as <u>secondary</u> measure to keep sediment onsite and to minimize vehicle and foot traffic beyond limits of site disturbance. Silt fencing must be keyed in.
- (6) Install <u>erosion control blankets</u> (see Slope Protection
- (7) Construct a concrete washout site adjacent to Clean as needed and remove at end of project.
- berm properly. (9) Use pea gravel bags around <u>drain inlets</u> located both

onsite and in autter.

(8) Cover all stockpiles and landscaped material and

- (10) Place port-a-potty near stabilized site entrance, behind curb and away from autters or storm drain inlets and water bodies.
- (II) Cover all exposed soil with straw mulch and tackifier (or equivalent).
- (12) Existing vegetation should be preserved as much as possible. Areas of disturbed soil/vegetation should be revegetated as soon as practical.
- Prevent equipment fluid leaks onto ground by placing drip pans or plastic tarps under equipment.

BMP'S, STORMWATER MANAGEMENT **PRACTICES**

A0.2

DR REV1:

11.21.2023

A L TECTL

ZU

OA

 \Box

S

EN A

S


ωщ


ш —


₩


0 1

0









EXCAVATION CHART (CUBIC YARDS) **GARAGE & PARKING** RESIDENCE (FOUNDATIONS)

RESIDENCE (BENEATH DECK)

TOTAL OFF-HAUL = 0 CU YARDS

SEE SHEET A1.3 FOR ADDITIONAL REQUIRED DRAINAGE MEASURES


CUT

0

GRADING & DRAINAGE NOTES:


- NO TREES TO BE REMOVED
- 2. ALL ROOF GUTTERS TO CONNECT TO DOWN SPOUTS AND DISCHARGE INTO ON-SITE RETENTION/INFILTRATION AREAS
- EXCESS CATCHMENT CAPACITY PROVIDED IN BIORETENTION BASINS TO ACCOUNT FOR DRIVEWAY IMPERVIOUS AREA. PER 2019 CBC J109.4 DRAINAGE ACROSS PROPERTY LINES SHALL NOT EXCEED THAT WHICH EXISTED PRIOR TO GRADING.
- 5. PROJECTS DISTURBS LESS THAN 1 ACRE AND THUS DOES NOT REQUIRE PERMIT TO COVER FOR DISCHARGES OF STORMWATER ASSOCIATED WITH
- PROJECT ARCHITECT/DESIGN ENGINEER SHALL CERTIFY TO THE COUNTY IN WRITING UPON THE COMPLETION OF WORK THAT ALL GRADING AND DRAINAGE IMPROVEMENTS AND FOUNDATIONS WERE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND FIELD DIRECTION AND SHALL REFERENCE THE BUILDING PERMIT NUMBER, ADDRESS AND APN#, SIGNED AND STAMPED BY THE CERTIFYING PROFESSIONAL
- 7. THE GROUND IMMEDIATELY ADJACENT TO THE FOUNDATION SHALL BE SLOPED AWAY FROM THE BUILDING AT 5% MIN SLOPE FOR 10 FEET MIN.
- ANY OFF-HAUL SHALL BE DISPOSED OF IN A LEGAL MANNER, EITHER AT MCNEAR BRICK AND BLOCK OR MARIN RESOURCE RECOVERY. 9. APPROX. 600 SF OF AREA TO BE DISTURBED DURING EXCAVATION & GRADING, WHICH INCLUDES REMOVAL OF PART OF THE ASPHALT DRIVEWAY WHICH WILL BECOME PERVIOUS AREA.
- 10. IMPERVIOUS SURFACES WITHIN 10' OF THE BUILDING SHALL BE SLOPED A MINIMUM OF 2% AWAY FROM THE BUILDING.


LEGEND



TREE TO BE REMOVED - NONE (SEE LANDSCAPE PLAN)

EXISTING TREE / SIGNIFICANT VEGETATION TO REMAIN (SEE LANDSCAPE PLAN)





PERMANENT SLOPE STABILIZATION STRATEGY:

- WHERE REQUIRED, UTILIZE REVERSE TERRACING (IN-SLOPE BENCHING) TO PROVIDE TEMPORARY RETENTION AND INFILTRATION MITIGATION WHILE EROSION CONTROL VEGETATION DEVELOPS. INSTALL STRAW-WATTLES AT 10'-14' SPACING, STAKED INTO HILLSIDE AT IN-SLOPE BENCHES, 10" WIDE TYPICAL. (NOT SHOWN ON DRAINAGE PLAN.)
- 2. APPLY 2-3" NATIVE COMPOST RAKED OVER GRADED HILLSIDE, FOLLOWED BY 1" INDIGENOUS MULCH AND/OR MULCH STRAW, FOLLOWED BY JUTE NETTING STAKED AT TOP AND BOTTOM EDGES. FINISH WITH LOCAL NATIVE GROUNDCOVER SEED MIX. LIMITIED WATERING MAY BE REQUIRED TO ESTABLISH INDIGENOUS GROWTH

ROADWAY NOTES:

1. NO WORK TO BE DONE TO THE EXISTING ROADWAY, EDGE OF PAVEMENT, EXISTING DRIVEWAY, PARKING AREAS, OR PEDESTRIAN APPROACHES.

GEOTECHNICAL CONDITIONS:

- ANY CONSTRUCTION DEBRIS OR ABANDONED UTILITIES ENCOUNTERED DURING SITE GRADING SHOULD BE REMOVED FROM THE SITE. ROCKS LARGER THAN 6 INCHES (150 MM) ENCOUNTERED DURING SUBGRADE PREPARATION OR SITE GRADING SHOULD BE REMOVED FROM THE SITE.
- 2. MATERIALS NON-EXPANSIVE SOIL AND ROCK MIXTURES GENERATED FROM ON-SITE EXCAVATIONS MAY BE SUITABLE FOR USE AS FILL PROVIDED THE MAXIMUM PARTICLE SIZES ARE LESS THAN FOUR INCHES AND THE SOIL HAS A MAXIMUM PI OF 15. PROCESSING WILL INCLUDE REMOVAL AND/OR CRUSHING OF ROCK, MIXING AND MOISTURE CONDITIONING AS DESCRIBED BELOW.
- COMPACTED FILL ON-SITE FILL, BACKFILL, AND SCARIFIED SUBGRADES SHOULD BE CONDITIONED WITHIN 2% OF THE OPTIMUM MOISTURE CONTENT. PROPERLY MOISTURE CONDITIONED AND CURED ON SITE MATERIALS SHOULD SUBSEQUENTLY BE PLACED IN LOOSE HORIZONTAL LIFTS OF 8-INCHES THICK OR LESS, AND UNIFORMLY COMPACTED TO AT LEAST 90 PERCENT RELATIVE COMPACTION. COMPACTED SURFACES SHOULD ALSO BE FIRM AND UNYIELDING UNDER HEAVY RUBBER-TIRED EQUIPMENT.
- 4. IMPORTED SELECT FILL IF IMPORTED FILL IS REQUIRED, THE MATERIAL SHALL CONSIST OF SOIL AND ROCK MIXTURES THAT SHALL BE FREE OF ORGANIC MATERIAL, HAVE A LIQUID LIMIT LESS THAN 40 AND A PLASTICITY INDEX LESS THAN 12, HAVE A MINIMUM R-VALUE OF 20, BE WELL-GRADED, AND CONSIST OF AT LEAST 50% SAND WITH 4-INCH MAXIMUM PARTICLE SIZES.
- 5. TEMPORARY SLOPES IN CONFORMANCE WITH OSHA'S CATEGORIZATION, THE ONSITE SOIL IS "TYPE C". THE CONTRACTOR MAY ELECT TO USE A VARIETY OF SHORING AND TEMPORARY SLOPE CONFIGURATIONS, BUT HIS OPERATIONS MUST CONFORM TO FEDERAL AND STATE OSHA REGULATIONS. THE SAFETY OF EXCAVATIONS, SLOPES, CONSTRUCTION OPERATIONS, AND PERSONNEL ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.



 $\mathbf{Z} \stackrel{ ext{T}}{\circ}$

OA

 \Box

₩




DR REV1: 11.21.2023

GRADING, DRAINAGE

& UTILITIES PLAN

3/32" = 1'-0"

A1.2



STORMWATER PROJEC	CT DATA FORM	
Project Name/Number	PROJECT ID #TBD	
Application Submittal Date [to be verified by municipal staff]	10/6/2023	R
Project Location	APN 048-101-26	F
[Street Address if available, or intersection and/or APN]	TOP OF REED ST.	R
Name of Owner or Developer	KATIE & JOE RAFFETTO	1/2 EXISTIN
Project Type and Description [Examples: "Single Family Residence," "Parking Lot	SINGLE FAMILY RESIDENCE	1/2 EXISTIN
Addition," "Retail and Parking"]		F
Total Project Site Area (acres)	88,862 SF, 2.04 ACRES	EXIS
Total New or Replaced Impervious Surface Area (square feet) [Sum of impervious area that will be constructed as part of the project]	453 SF NEW IMPERVIOUS AREA	DRIV
Total Pre-Project Impervious Surface Area	6975 SF	
Total Post-Project Impervious Surface Area	7428 SF	*NOTE: EQI
Runoff Reduction Measures Selected	🛚 1. Disperse runoff to vegetated area	CONTAIN (
(Check one or more)	2. Pervious pavement	CALCULAT

3. Cisterns or Rain Barrels

DMA NAME	AREA (SF)	POST-PROJECT	RUNOFF	DMA AREA X	RETENTION	SIZING	MIN FACILITY	PROPOSED
		SURFACE	FACTOR	RUNOFF FACTOR	AREA	FACTOR	SIZE (SF)	SIZE (SF)
				(SF) [A]				
ROOF SOUTH**	660	ROOF	1	660	#1	0.5	330	>535 SF
ROOF EAST**	884	ROOF	1	884	#2	0.5	442	>647 SF
ROOF WEST**	1248	ROOF	1	1248	#3	0.5	624	>624 SF
1/2 EXISTING REAR STONE PATIO	410	HARDSCAPE	1	410	#1	0.5	205	>535 SF
1/2 EXISTING REAR STONE PATIO	410	HARDSCAPE	1	410	#2	0.5	205	>647 SF
FRONT PATIO	491	HARDSCAPE	1	491	#4	0.5	245.5	>246 SF
EXISTING ASPHALT	4231	PAVING	1	4231	#5	0.04	169.24	*169 equiv
DRIVEWAY/CARPORT								

(1) 50GALLON DRYWELL (NDS FLOW-WELL) WITH GRAVEL BACKFILL AT SIDES AND BENEATH. VOLUME OF BACKFILL SHALL BE

**SELF-RETAINING AREAS HAVE A SIZING FACTOR OF 1/2, PER BASMAA PAGE 4-4: "MAXIMUM RATIO IS 2 PARTS IMPERVIOUS FOR EVERY 1 PART

TEMPORARY EROSION CONTROL MEASURES:

SHALL BE RESPONSIBLE FOR THE REPAIR OF THE SAME.

GENERAL EROSION CONTROL NOTES:

SEDIMENT

STORMWATER POLLUTION.

1. CONTRACTOR TO COMPLY WITH MCC 24.04.625 FOR EROSION AND

2. PROTECT EXISTING STORM DRAIN FACILITIES AT ALL TIMES FROM EXCESS

3. THE CONTRACTOR SHALL MAINTAIN A CLEAN SITE AT ALL TIMES WHICH IS FREE OF ALL DEBRIS, HAZARDOUS WASTES, AND STOCKPILED MATERIALS

PER MCC 23.18.093, THE CONTRACTOR SHALL PREVENT STORMWATER

STORMWATER POLLUTION FROM CONSTRUCTION-RELATED ACTIVITIES

EXISTING FACILITY IN THE PUBLIC R.O.W. BEYOND NORMAL WEAR AND

TEAR, AS DETERMINED BY THE PUBLIC WORKS AGENCY, THE PERMITTEE

POLLUTION FOR THE DURATION OF THE PROJECT. THE CONTRACTOR SHALL CONFORM TO THE "BEST MANAGEMENT PRACTICES" PUBLISHED BY CASQA

PER MCC 24.04.016 IF CONSTRUCTION ACTIVITY CAUSES DAMAGE TO ANY

UNLESS APPROVED BY THE PROJECT ARCHITECT. ALL APPROVED STOCKPILES SHALL BE COVERED AND PROTECTED TO PREVENT

(CALIFORNIA STORMWATER QUALITY ASSOCIATION) TO PREVENT

SEDIMENT CONTROL AND MCC 24.04.627 FOR SURFACE RUNOFF POLLITION

- I. EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO CONSTRUCTION AND SHALL BE MAINTAINED BY THE CONTRACTOR IN PROPER WORKING ORDER THROUGHOUT THE FIRST WINTER. THIS PROTECTION SHALL CONSIST OF APPROPRIATE FILTER FENCES, DIVERSION BERMS, STRAW BALE DIKES, ETC. THESE DEVICES SHALL BE PLACED IN ORDER TO MINIMIZE EROSION AND TO COLLECT SEDIMENT GENERATED BY THE CONSTRUCTION OF THIS PROJECT. EXCEPT FOR PAVED AND LANDSCAPED AREAS ALREADY COMPLETED, ALL GRADED AREAS SHALL BE HYDROSEEDED IN ORDER TO PREVENT EROSION OF BARE EARTH. ALL EROSION CONTROL FACILITIES SHALL CONFORM TO THE "MANUAL OF STANDARDS FOR EROSION & SEDIMENT CONTROL MEASURES," AS PUBLISHED BY THE ASSOCIATION OF BAY AREA GOVERNMENTS, LATEST EDITION.
- 2. STABILIZE ALL DENUDED AREAS AND MAINTAIN EROSION CONTROL MEASURES CONTINUOUSLY BETWEEN OCTOBER 1 AND MAY 1. CONDUCT ROUTINE INSPECTIONS OF EROSION CONTROL MEASURES, ESPECIALLY BEFORE AND AFTER RAINSTORMS, AND MAKE REPAIRS AS NECESSARY
- REMOVE SOILS PROMPTLY, AND AVOID STOCKPILING OF FILL MATERIALS WHEN RAIN IS FORECAST. IF RAIN THREATENS, STOCKPILED SOILS AND OTHER MATERIALS SHOULD BE TARPED AT THE REQUEST OF THE CITY ENGINEER.
- 4. STORE, HANDLE AND DISPOSE OF CONSTRUCTION MATERIALS AND WASTES SO AS TO AVOID THEIR ENTRY TO THE STORM SYSTEM. CONTRACTOR MUST NOT ALLOW CONCRETE, WASHWATERS, SLURRIES, PAINT OR OTHER MATERIALS TO ENTER CATCH BASINS OR TO ENTER SITE RUNOFF.
- THE CONTRACTOR SHALL STABILIZE THE SITE ENTRANCE WITH 3" +/- OF CRUSHED ROCK AND PLACE REMOVEABLE HAYROLLS AT THE INTERFACE UNTIL FINAL PAVING.
- 6. PLACE AND MAINTAIN SAND/GRAVEL BAGS AROUND ALL DRAINAGE INLETS AND CATCH BASINS AS LAST LINE OR PREVENTION. INSPECT AND MAINTAIN DURING WINTER STORMS.
- 7. PLACE AND MAINTAIN RUBBLE/RIPRAP AT DISCHARGE OF MAJOR DRAINS. KEY/ANCHOR RUBBLE APRONS MAY BE CONSTRUCTED FROM EITHER STONE OR BROKEN CONCRETE AND KEYED (EXCAVATED) INTO SLOPES AS NEEDED TO PREVENT MOVEMENT.
- EXCAVATED SLOPES SHALL BE COVERED WITH A PROTECTIVE NETTING I.E. JUTE, STRAW, OR EXCELSIOR MATTING OR MULCH NETTING. APPLY PARALLEL TO DIRECTION OF FLOW ON STEEP SLOPES AND ANCHOR SECURELY, INSPECT AND REPAIR AS NEEDED.
- 9. USE FILTRATION OR OTHER MEASURES TO REMOVE SEDIMENT FROM DEWATERING EFFLUENT.
- 10. INSTALL FILTER FABRIC BAGS INSIDE ALL CATCH BASINS & MAINTAIN DURING WINTER STORMS.

CONSTRUCTION WASTE MANAGEMENT:

- 1. STORE, HANDLE, AND DISPOSE OF CONSTRUCTION MATERIALS AND WASTES SO AS TO AVOID THEIR ENTRY TO THE STORM SYSTEM. CONTRACTOR MUST NOT ALLOW CONCRETE, WASHWATERS, SLURRIES, PAINT OR OTHER MATERIALS TO ENTER CATCH BASINS OR TO ENTER SITE RUNOFF.
- 2. CLEANING, FUELING, OR MAINTAINING VEHICLES SHALL NOT BE PERFORMED ON-SITE.
- 3. USE OF PESTICIDES AND/OR FERTILIZERS, WHEN APPLIED, SHALL BE CONTROLLED TO PREVENT POLLUTION RUNOFF.

- 1. ALL AREAS OF CUT, FILL AND UNGRADED AREAS DISTURBED BY THE
- 2. LANDSCAPING AND GROUNDCOVER SHALL BE PLANTED AFTER ALL WORK HAS BEEN COMPLETED. THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR FURNISHING LABOR AND MATERIALS TO ACCOMPLISH A DENSE PLANT
- 3. INSPECT AND CLEAN OUT DEBRIS FROM ALL CATCH BASINS. MAINTAIN FILTER FABRIC BAGS (INSIDE CATCH BASINS) BEFORE AND AFTER WINTER
- 4. PERIODICALLY CONDUCT ROUTINE INSPECTIONS OF ALL EROSION CONTROL MEASURES ESPECIALLY BEFORE AND AFTER RAINSTORMS AND MAKE REPAIRS IF NECESSARY. EXAMINE ALL STORM, PERIMETER AND FOUNDATION DRAIN EFFLUENTS. PERIODICALLY CLEAN AND INSPECT GUTTERS, CATCH BASINS, DRAINAGE INLETS, DIVERSION DITCHES, SILT FENCING, SEDIMENT STOP INSTALLATION. PERIODICALLY TEST OPERATION AND FUNCTIONALITY OF DRAINAGE SYSTEMS.


NAME	AREA (SF)	POST-PROJECT	RUNOFF	DMA AREA X	RETENTION	SIZING	MIN FACILITY	PROPOSED
		SURFACE	FACTOR	RUNOFF FACTOR (SF) [A]	AREA	FACTOR	SIZE (SF)	SIZE (SF)
OUTH**	660	ROOF	1	660	#1	0.5	330	>535 SF
EAST**	884	ROOF	1	884	#2	0.5	442	>647 SF
WEST**	1248	ROOF	1	1248	#3	0.5	624	>624 SF
R STONE PATIO	410	HARDSCAPE	1	410	#1	0.5	205	>535 SF
R STONE PATIO	410	HARDSCAPE	1	410	#2	0.5	205	>647 SF
PATIO	491	HARDSCAPE	1	491	#4	0.5	245.5	>246 SF
ASPHALT (CARPORT	4231	PAVING	1	4231	#5	0.04	169.24	*169 equiv

QUIVALENT AREA OF PROPOSED BIORETENTION BASIN WILL BE CONFIRMED WITH MANUFACTURER. EACH BIORETENTION AREAS SHALL CALCULATED TO PROVIDE EQUIVALENT RETENTION AREA

PERVIOUS AREA.'

PROJECT

NORTH




STORMWATER CONTROL PLAN DIAGRAM

3/32" = 1'-0"

STORMWATER CONTROL STRATEGY / DRAINAGE PLAN:

- 1. THE TOTAL LOT AREA IS 88,862 SF. WHICH CURRENTLY INCLUDES 6975 SF OF IMPERVIOUS AREA, WHICH AMOUNTS TO 8% OF THE LOT AREA. PROPOSED DEVELOPMENT WILL RESULT IN AN OVERALL INCREASE OF IMPERVIOUS AREA OF 453SF, RESULTING IN 7428SF OF IMPERVIOUS AREA.
- 2. RUNOFF FROM IMPERVIOUS ROOFS WILL BE DIRECTED TO SELF-RETAINING PERVIOUS LANDSCAPE AREAS SURROUNDING THE HOUSE.
- 3. RUNOFF FROM THE EXISTING IMPERVIOUS PAVED DRIVEWAY WILL BE COLLECTED IN A PIPED DRAINAGE SYSTEM AND DIRECTED TO ON-SITE BIO-RETENTION BASINS WITH DRY WELLS.
- THE BIO-RETENTION BASINS WITH DRY WELLS SHALL BE SIZED ACCORDING TO THE AREA OF THE DRAINAGE MANAGEMENT AREA AS SHOWN IN THE CHART TO THE RIGHT, PER MANUFACTURER'S RECOMMENDATIONS, WITH APPROPRIATE VOLUME OF GRAVEL BACKFILL.
- FOUNDATION DRAINS DISPERSE TO VEGETATED AREAS ON THE SOUTH, EAST AND WEST SIDES OF THE HOUSE.
- 8. THE PROPOSED CONSTRUCTION OF A BIO-RETENTION BASINS, DRY-WELLS AND PERVIOUS AREAS WILL INFILTRATE RUNOFF AND PROVIDE IMPROVED ON-SITE STORMWATER RUNOFF CONTROL COMPARED TO EXISTING CONDITIONS DRAINAGE OFF THE PROPERTY SHALL NOT EXCEED THAT WHICH EXISTED PRIOR TO GRADING (CBC 1804.3).
- 9. SEE SHEET A0.2 FOR OTHER POST-CONSTRUCTION STORMWATER CONTROL AND MAINTENANCE PRACTICES.



A L

ZT

 \Box

 O^{2}

N 9 4 9

ESID Y CA

<u>м</u>

ш —

	ISSUED
	DR REV1: 11.21.2023

STORMWATER CONTROL PLAN & CONSTRUCTION MANAGEMENT

A1.3


3/32" = 1'-0"

PERMANENT EROSION CONTROL MEASURES:

GRADING OPERATION SHALL BE HYDROSEEDED AND/OR HYDROMULCHED WITH A CITY AND/OR COUNTY APPROVED NATIVE CALIFORNIA MIX.

COVER FOR EROSION CONTROL

STORMS.



A L TECTU Z OA \Box S


> CE 94 9 4 P ESID Y CA <u>м</u> ш **₩**


~ ⊢

DR REV1: 11.21.2023

3/32" = 1'-0"

A1.4





FIRST FLOOR PLAN KEY NOTES

THAN 36 INCHES.

- PROVIDE GAS SHUTOFF WITHIN 6' OF APPLIANCES. VENT FROM KITCHEN HOOD TO ROOF 3' MIN. FROM PROPERTY LINE
- RELOCATE GAS METER NEW STAIRS: RISER MAX HT: 7.75", TREAD DEPTH: 11". BOTTOM LANDINGS OF STAIRS: THE WIDTH PERPENDICULAR TO THE DIRECTION OF TRAVEL SHALL BE NOT LESS THAN THE WIDTH OF THE FLIGHT SERVED. WHERE THE STAIRWAY HAS A STRAIGHT RUN, THE DEPTH IN THE DIRECTION OF TRAVEL SHALL BE NOT LESS
- 4. CONTINUOUS HANDRAIL @ 36" ABOVE STAIR NOSING PER CRC R311.7.8, SEE

DETAIL 7/A6.0

- 5. WOOD GUARDRAIL, 36" ABOVE STAIR NOSINGS AND 42" ABOVE ALL LANDINGS AND DECKS. NO 4" SPHERE SHALL PASS
- 6. NEW DISHWASHER SHALL BE ENERGY STAR RATED USING 4.25 GALLONS OF WATER PER CYCLE AND A MAXIMUM 295 KILOWATT-HOURS PER YEAR AND PROVIDED WITH AN APPROVED AIR GAP @ SINK.
- 7. TYPICAL DECKING AND EXTERIOR STAIR MATERIAL TO BE 2X6 CON HEART REDWOOD, LISTING 8110-2084:0002 BY CA STATE FIRE MARSHALL FOR WUI COMPLIANCE WITH CLASS B FLAME SPREAD.


PROJECT NORTH

- 8. (N) LAUNDRY HOOKUPS: PROVIDE 220V, AND 120V, DRAINS AND SUPPLIES. GAS DRYER, PROVIDE GAS SHUTOFF WITHIN 6'.
- 9. (N) CABINETRY.
- 10. FRONT PATIO AND STAIRS ARE AT GRADE, NO GUARDRAIL. PROVIDE HANDRAIL FOR STAIRS WITH >3 RISERS.
- 11. LOWER CEILING, (R) SKYLIGHT, (N) VANITY, WOOD FLOORS, AND (N) FAUCET
- 12. (N) ROOF AT (N) PORCH AREA
- 13. REMODEL KITCHEN: NEW FINISHES, FIXTURES, LIGHTING, CABINETRY
- 14. RANGE HOOD SHALL VENT TO EXTERIOR THROUGH ROOF 15. REMODEL BATHROOM: NEW FINISHES, FIXTURES, LIGHTING, AND VANITY
- 16. SHOWER CURB, SEE DETAIL 7/A6.0
- 17. NEW AREA DRAIN, SLOPE AREA DRAIN $\frac{1}{4}$ " PER FT

- 18. NON-ABSORBANT FINISHES TO 72" AFF AND SLOPE SHOWER FLOOR $\frac{1}{4}$ " PER FT. TO DRAIN
- 19. (N) GLASS SHOWER SURROUND TO BE TEMPERED, WITH LOW IRON (STARPHIRE) GLASS.
- 20. THE EGRESS DOOR SHALL PROVIDE A CLEAR WIDTH OF NOT LESS THAN 32" WHERE MEASURED BETWEEN THE FACE OF THE DOOR AND THE STOP, WITH THE DOOR OPEN 90 DEGREES.


A L D ZÜ OA


ESIDENCE FY CA 94941



NEW TYP. NON-RATED WALL

1-HOUR RATED WALL: 1 LAYER TYPE X $\frac{5}{8}$ " GWB EACH SIDE








- 1. NEW 8'-0" WIDE, 7'-0" TALL POCKET DOOR IN NEW FRAMED, NON-LOAD
- BEARING WALL TO PLAYROOM
- NEW BUILT-IN CABINETRY CLOSETS
 FURR OUT EXISTING WALLS W/ NEW DRYWALL TO LEVEL 4 TO MAKE WALL
- FLAT.

 4. NEW FULL BATH BENEATH NEW SHED DORMER ADDITION.
- 5. SHOWER CURB, SEE DETAIL 7/A6.0
- 6. NEW AREA DRAIN, SLOPE AREA DRAIN $\frac{1}{4}$ " PER FT
- 7. NON-ABSORBANT FINISHES TO 72" AFF AND SLOPE SHOWER FLOOR $\frac{1}{4}$ " PER FT.

TO DRAIN

- 8. (N) GLASS SHOWER SURROUND TO BE TEMPERED, WITH LOW IRON
- (STARPHIRE) GLASS

 9. EGRESS-COMPLIANT WINDOWS IN ALL SLEEPING AREAS: 5.4SF MIN CLEAR, 44" MAX SILL HEIGHT, 20" MIN CLEAR WIDTH




Z

 $O_{\frac{4}{5}}$

S

TRUE NORTH



WALL LEGEND:

EXISTING WALLS TO REMAIN

ZZZZZ EXISTING WALLS TO BE REMOVED

 $\square \square \square \square \square$ existing elements to be removed

NEW TYP. NON-RATED WALL

1-HOUR RATED WALL: 1 LAYER TYPE X 5/8" GWB EACH SIDE PROPOSED SECOND FLOOR PLAN

A2.3


1/4" = 1'-0"


SECOND FLOOR PROPOSED PLAN


1/4" = 1'-0"


Z

PROJECT NORTH










CERTAINTEED LANDMARK PRO CLASS-A RATED ASPHALT SHINGLES IN MOIRE BLACK



EXTERIOR SIDING: FIRE-TREATED STAINED SHINGLES TO MATCH EXISTING



EXTERIOR TRIM COLOR: BM 2128-10 - BLACK BEAUTY



CLAD WOOD WINDOWS IN MARVIN BRONZE TO MATCH EXISTING




TYPICAL EXTERIOR WALL SCONCE DOWNWARD DIRECTED, LED



Bedford Wide Tall 3/4 Lantern Item # CHO 2157NC

Designer: Chapman & Myers

Height: 24" Width: 9.75" Extension: 6" Backplate: 8.25" x 14.75" Finishes: NC Glass Options: CG Socket: 2 - E12 Candelabra Wattage: 2 - 60 C11 Weight: 12 Pounds ©EFC DESIGNS



TYPICAL EXTERIOR STEP LIGHT DOWNWARD DIRECTED, LED



Product Information

Brand: Kichler Brand Category: Landscape 12V LED Deck Shipping Method: Ground SKU: 16110CO27 UPC: 783927459280

Electrical and Operational Information Color Temperature: 2700K Dimmable: No Lamping Category: LED Lamping Included: Bulbs Included Lumens: 41 Primary Number of Bulbs: 1 Total Number of Bulbs: 1 Total Watts: 2.5 Voltage: 12

Wattage Max: 0.86

Dimensions and Measurements Weight: 0.4875 Width: 3.25

Country of Origin: CN UL Ratings: cETLus Listed Wet

Additional Details

Warranty and Specifications

 Slope Ceiling Kit: N
 Ceiling Wall Mount Included: N Install Glass Up or Down: N
 Low Ceiling Adaptable: N Material: Copper

Vindows	Location	Туре	Brand/Model	Product Size		Placement		Notes
				Width (in)	Height (in)	Sill Height (in)	Head Height (in)	
101	MUDROOM 102	CASEMENT	ALUM-CLAD WD	24	29	51	80	NEW
102	SUNROOM 103	CASEMENT	ALUM-CLAD WD	24	54	26	80	NEW
103	SUNROOM 103	CASEMENT	ALUM-CLAD WD	24	54	26	80	NEW
104	SUNROOM 103	CASEMENT	ALUM-CLAD WD	24	54	26	80	NEW
105	SUNROOM 103	CASEMENT	ALUM-CLAD WD	24	54	26	80	NEW
106	SUNROOM 103	CASEMENT	ALUM-CLAD WD	24	54	26	80	NEW
107	SUNROOM 103	CASEMENT	ALUM-CLAD WD	24	54	26	80	NEW
108	SUNROOM 103	CASEMENT	ALUM-CLAD WD	24	54	26	80	NEW
109				OMITTED				
110				OMITTED				
111	KITCHEN 104	CASEMENT	ALUM-CLAD WD	22	37	43	80	EXISTING TO REMAIN
112	KITCHEN 104	FIXED	ALUM-CLAD WD	46	37	43	80	EXISTING TO REMAIN
113	DINING 105	CASEMENT	ALUM-CLAD WD	22	37	43	80	EXISTING TO REMAIN
114	DINING 105	CASEMENT	ALUM-CLAD WD	33	66	8	74	EXISTING TO REMAIN
115	DINING 105	FIXED	ALUM-CLAD WD	33	66	8	74	EXISTING TO REMAIN
116	DINING 105	CASEMENT	ALUM-CLAD WD	33	66	8	74	EXISTING TO REMAIN
117	MAIN BEDROOM 107	CASEMENT	ALUM-CLAD WD	24	52	24	76	EXISTING TO REMAIN
	MAIN BEDROOM 107	FIXED	ALUM-CLAD WD	42	52	24	76	EXISTING TO REMAIN
119	MAIN BEDROOM 107	CASEMENT	ALUM-CLAD WD	24	52	24	76	EXISTING TO REMAIN
120	STORAGE	CASEMENT	ALUM-CLAD WD	24	24	52	76	EXISTING TO REMAIN
201	OFFICE 201	CASEMENT	ALUM-CLAD WD	36	42	28	70	NEW
202	OFFICE 201	CASEMENT	ALUM-CLAD WD	24	42	28	70	NEW
203	OFFICE 201	CASEMENT	ALUM-CLAD WD	24	42	28	70	NEW
204	OFFICE 201	CASEMENT	ALUM-CLAD WD	24	42	28	70	NEW
205	OFFICE 201	CASEMENT	ALUM-CLAD WD	24	42	28	70	NEW
206	OFFICE 201	CASEMENT	ALUM-CLAD WD	36	40	28	68	NEW
207	BED 202	CASEMENT	ALUM-CLAD WD	31	40	28	68	NEW
208	BED 202	CASEMENT	ALUM-CLAD WD	31	40	28	68	NEW
209	BED 202	CASEMENT	ALUM-CLAD WD	31	40	28	68	NEW
210	BED 203	CASEMENT	ALUM-CLAD WD	28	30	38	68	EXISTING TO REMAIN
	BED 203	CASEMENT	ALUM-CLAD WD	30	40	28	68	EXISTING TO REMAIN
	BED 203	FIXED	ALUM-CLAD WD	53	58	19	77	EXISTING TO REMAIN
	BED 203	CASEMENT	ALUM-CLAD WD	30	40	28	68	EXISTING TO REMAIN
	LIBRARY 205	CASEMENT	ALUM-CLAD WD	17	30	38	68	EXISTING TO REMAIN
	LIBRARY 205	CASEMENT	ALUM-CLAD WD	30	60	33	93	EXISTING TO REMAIN
	LIBRARY 205	FIXED	ALUM-CLAD WD	53	65	33	98	EXISTING TO REMAIN
	LIBRARY 205	CASEMENT	ALUM-CLAD WD	30	60	33	93	EXISTING TO REMAIN
	LIBRARY 205	CASEMENT	ALUM-CLAD WD	17	30	38	68	EXISTING TO REMAIN
	BED 206	CASEMENT	ALUM-CLAD WD	30	40	28	68	EXISTING TO REMAIN
		FIXED						
	BED 206		ALUM-CLAD WD	52	58	19	77	EXISTING TO REMAIN
	BED 206	CASEMENT	ALUM-CLAD WD	30	40	28	68	EXISTING TO REMAIN
	BED 206	CASEMENT	ALUM-CLAD WD	29	40	28	68	EXISTING TO REMAIN
	BED 206	CASEMENT	ALUM-CLAD WD	28	40	28	68	EXISTING TO REMAIN
	BATH 207	CASEMENT	ALUM-CLAD WD	24	32	36	68	EXISTING TO REMAIN
	BATH 207	CASEMENT	ALUM-CLAD WD	29	37	31	68	EXISTING TO REMAIN
	OFFICE 208	DBL CASEMENT	ALUM-CLAD WD	59	37	31	68	EXISTING TO REMAIN
	STAIRS	FIXED	ALUM-CLAD WD	36	72	0	72	EXISTING TO REMAIN
	STAIRS	FIXED	ALUM-CLAD WD	28	72	0	72	EXISTING TO REMAIN
	STAIRS	FIXED	ALUM-CLAD WD	28	51	0	51	EXISTING TO REMAIN
230	BATH 210	CASEMENT	ALUM-CLAD WD	30	40	28	68	NEW
231	BATH 210	CASEMENT	ALUM-CLAD WD	30	40	28	68	NEW
232	BATH 210	CASEMENT	ALUM-CLAD WD	30	40	28	68	NEW
	NOTES:	All typical new wir	dows to be Jeld-Wen alum	inum clad woo	d windows, wi	th primed woo	d interior and	exterior in MARVIN BRO
			wner. Alternate brands suc	h as Marvin, An	dersen, Loewe	en are accepto	able alternates	5.
ior Doors	Location	Туре	Material/Spec	Produ Width (in)	ct Size Height (in)			Notes
101	ENTRY 101	INSWING	JELD-WEN CLAD WOOD	36	84			NEW
114	DINING 105	FRENCH	JELD-WEN CLAD	72	84			NEW
115	SUN ROOM 103	FRENCH	JELD-WEN CLAD	75	84			NEW
213	STAIRS	OUTSWING	JELD-WEN CLAD	33	84			EXISTING TO REMAIN
2.0		i.	WOOD	1	I.	I		i de la companya de

ONALD ARCHITECTURE S

RAFFETTO RESIDENCE REET, MILL VALLEY CA 94941 APN #048-101-26

REE



ISSUED

DR REV1:
11.21.2023

MATERIALS BOARD & SCHEDULE

3/16" = 1'-0"

A5.1

