















GENERAL

THE DESIGN PROFESSIONAL WHO PREPARED THESE DRAWINGS IS NOT RESPONSIBLE FOR THE MISUSE OF, OR UNAUTHORIZED CHANGES MADE TO THESE DRAWINGS...

THE CONTRACTOR SHALL:

FURNISH AND INSTALL MATERIALS IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS OF THE CITIES AND COUNTY OF MARIN DATED JUNE 1992...

OBTAIN RELEVANT PERMITS AND APPROVALS REQUIRED BY GOVERNING AGENCIES PRIOR TO COMMENCING WORK.

ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION FOR THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY...

HOLD HARMLESS, INDEMNIFY AND DEFEND THE OWNER, THE DESIGN PROFESSIONAL, THEIR CONSULTANTS AND THE COUNTY OF MARIN, FROM LIABILITY, REAL OR ALLEGED IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT...

SUBMIT A TRAFFIC CONTROL PLAN TO THE DEPARTMENT OF PUBLIC WORKS AND OBTAIN APPROVAL PRIOR TO COMMENCING WORK IN THE PUBLIC RIGHT-OF-WAY.

PROVIDE A PROPERLY SIGNED ALTERNATE ACCESSIBLE ROUTE OF TRAVEL IF CONSTRUCTION ACTIVITIES IMPACT PEDESTRIAN ACCESS. THIS REQUIREMENT APPLIES CONTINUOUSLY, AND IS NOT LIMITED TO NORMAL WORKING HOURS.

CONTACT UNDERGROUND SERVICE ALERT (811) AT LEAST 48-HOURS BEFORE EXCAVATING.

PROPERLY MUFFLE EQUIPMENT AND LIMIT CONSTRUCTION HOURS TO 7:00 AM TO 6:00 PM MONDAY THROUGH FRIDAY, AND 9:00 AM TO 6:00 PM ON SATURDAY, EXCLUDING HOLIDAYS...

REPAIR DAMAGE TO FACILITIES OCCURRING AS A RESULT OF CONSTRUCTION ACTIVITIES TO RETURN THEM TO THEIR CONDITION PRIOR TO CONSTRUCTION. IF THE CONTRACTOR DOES NOT ACT PRUDENTLY, THE COUNTY OF MARIN MAY, AT ITS DISCRETION PERFORM THE CORRECTION AND CHARGE THE CONTRACTOR FOR COSTS INCURRED.

REMOVE STUMPS AND ROOT FROM THE SOIL TO A DEPTH OF AT LEAST 12-INCHES BELO THE SURFACE OF THE GROUND IN THE AREA TO BE OCCUPIED BY THE BUILDING.

PROVIDE RECORD DRAWINGS TO THE OWNER'S REPRESENTATIVE WHICH INCLUDE IMPROVEMENTS WHICH DEViate FROM AND IMPROVEMENTS NOT SHOWN ON THE ORIGINAL DESIGN DRAWINGS.

GRADING

PERFORM GRADING IN CONFORMANCE WITH CHAPTER 18 AND APPENDIX J OF THE 2019 EDITION OF THE CALIFORNIA BUILDING CODE, AND THE RECOMMENDATIONS CONTAINED IN THE GEOTECHNICAL REPORT PREPARED BY KC ENGINEERING, DATE NOVEMBER 6, 2023.

PROVIDE PROTECTIVE FENCE AROUND THE DRIP LINES OF TREES WHICH WILL REMAIN FOLLOWING CONSTRUCTION PRIOR TO PERFORMING GRADING OPERATIONS. RETAIN THE SERVICES OF A COUNTY OF MARIN APPROVED ARBORIST PRIOR TO DISTURBING EARTH WITHIN THE ROOT ZONES OF TREES WHICH WILL REMAIN FOLLOWING CONSTRUCTION...

PROVIDE A MOISTURE BARRIER IN AREAS WHERE CURB AND GUTTER ARE ADJACENT TO LANDSCAPING AND WHERE THE SOIL EXPANSION INDEX IS GREATER THAN 51.

REMOVE MATERIAL WHICH WILL NOT BE USED ON SITE AS IT IS EXCAVATED AND DISPOSE OF IN ACCORDANCE WITH THE GOVERNING AGENCY'S REQUIREMENTS.

MAINTAIN A CLEAN CONSTRUCTION SITE TO PREVENT THE INTRODUCTION OF FOREIGN MATERIALS INTO THE STORM WATER CONVEYANCE SYSTEM. ACTIVITY DURING CONSTRUCTION WHICH RESULTS IN THE DISCHARGE OF POLLUTANTS TO THE STORM WATER CONVEYANCE SYSTEM IS IN VIOLATION OF THE COUNTY OF MARIN CODE OF ORDINANCES AND THE SAN FRANCISCO BAY REGIONAL WATER QUALITY CONTROL BOARD'S REGULATIONS.

PROVIDE DUST CONTROL THROUGHOUT THE DURATION OF THE CONSTRUCTION PROJECT TO MINIMIZE AIRBORNE POLLUTANTS.

STOP WORK IF CONTAMINATED MATERIAL IS ENCOUNTERED. PREPARE A WORK PLAN AND ACQUIRE APPROVAL IN WRITING FROM THE MARIN COUNTY FIRE DEPARTMENT AND THE SAN FRANCISCO BAY REGIONAL WATER QUALITY CONTROL BOARD PRIOR TO RESUMING WORK.

IF, DURING THE COURSE OF CONSTRUCTION, CULTURAL, ARCHAEOLOGICAL OR PALEONTOLOGICAL RESOURCES ARE UNCOVERED AT THE SITE (SURFACE OR SUBSURFACE RESOURCES) WORK SHALL BE HALTED IMMEDIATELY WITHIN 50 METERS (150 FEET) OF THE FIND UNTIL IT CAN BE EVALUATED BY A QUALIFIED PROFESSIONAL ARCHAEOLOGIST...

THE CALIFORNIA BUILDING CODE REQUIRES THAT MATERIALS USED FOR THE CONSTRUCTION OF PERMANENT STRUCTURES LOCATED NEARER THAN 6-INCHES TO EARTH BE TREATED, OR OF NATURAL RESISTANCE TO DECAY. ELEVATIONS HAVE BEEN ESTABLISHED WITH THIS SET OF CIVIL DRAWINGS, WHICH MAY REQUIRE THE IMPLEMENTATION OF A RAISED CURB ALONG THE PERIMETER OF THE BUILDING WHERE ADJACENT TO LANDSCAPE AREAS...

THE CONTRACTOR SHALL NOT IMPEDE DRAINAGE FROM EXISTING UPSTREAM PROPERTIES. THE CONTRACTOR SHALL PLACE STOCKPILES AWAY FROM CREEK SETBACKS, AWAY FROM VEGETATION DESIGNATED TO REMAIN, A MINIMUM OF 10-FEET FROM ADJACENT EXISTING RESIDENTIAL PARCELS, AND A MINIMUM OF 50-FEET FROM ADJACENT EXISTING RESIDENTIAL PARCELS WHERE THE STOCK PILE DEPTH EXCEEDS 2.5- FEET.

A PROTECTION ZONE SHALL BE ESTABLISHED TO PROTECT NATURAL VEGETATION AND TREES (WHICH WILL REMAIN FOLLOWING CONSTRUCTION) FROM CONSTRUCTION ACTIVITIES. THE FOLLOWING CONDITIONS AND RESTRICTIONS SHALL APPLY:

- I. THE ZONE SHALL ENCOMPASS THE "PROTECTED PERIMETER" WHICH SHALL BE EITHER THE ROOT ZONE OR OTHER LIMIT AS ESTABLISHED IN THIS APPROVAL.
II. THE ZONE SHALL BE DELINEATED WITH A BRIGHTLY COLORED CONSTRUCTION FENCE. SUCH FENCES SHALL REMAIN CONTINUOUSLY IN PLACE FOR THE DURATION OF ALL WORK UNDERTAKEN ON THE SITE.

- III. NO STORAGE OR CONSTRUCTION ACTIVITIES (INCLUDING TRENCHING, GRADING OR FILLING) SHALL BE PERMITTED WITHIN THE PROTECTED ZONE.
IV. NO BURNING OR USE OF EQUIPMENT WITH AN OPEN FLAME SHALL OCCUR NEAR OR WITHIN THE PROTECTED PERIMETER.
V. BRUSH, EARTH AND OTHER DEBRIS SHALL BE REMOVED IN A MANNER WHICH PREVENTS INJURY TO THE PROTECTED TREES AND/OR SHRUBS.
VI. NO OIL, GAS, CHEMICALS OR OTHER SUBSTANCES THAT MAY BE HARMFUL TO TREES SHALL BE STORED OR DUMPED WITHIN THE PROTECTED PERIMETER OR ANY OTHER LOCATION FROM WHICH SUBSTANCES MIGHT ENTER THE PERIMETER OF A PROTECTED TREE.

THE PROTECTION ZONE DELINEATED WITH THE BRIGHTLY COLORED CONSTRUCTION FENCE SHALL BE POSTED WITH SIGNS WHICH STATE "TREE/VEGETATION PROTECTION ZONE-NO CONSTRUCTION OR STORAGE PERMITTED." ANY SPECIAL WORK, INCLUDING MITIGATION, WITHIN THE "PROTECTION ZONE" MUST BE DONE UNDER THE SUPERVISION OF A COUNTY APPROVED CERTIFIED ARBORIST.

SEE ARBORIST'S REPORT FOR THE TREES TO BE REMOVED OR PROTECTED.

THE ENGINEER SHALL CERTIFY TO THE COUNTY IN WRITING UPON THE COMPLETION OF WORK THAT ALL GRADING AND DRAINAGE IMPROVEMENTS WERE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND FIELD DIRECTION. BE AWARE THAT A DEPARTMENT OF PUBLIC WORKS ENGINEER WILL NEED TO INSPECT AND ACCEPT WORK AFTER RECEIPT OF THE CERTIFICATION LETTER. CERTIFICATION LETTERS SHALL REFERENCE BUILDING PERMIT NUMBER OR NUMBERS FOR SPECIFIC WORK BEING CERTIFIED, THE ADDRESS OF THE PROPERTY AND THE ASSESSOR'S PARCEL NUMBER (APN), AND SHALL BE SIGNED AND STAMPED BY THE CERTIFYING PROFESSIONAL.

UTILITIES

THE CONTRACTOR SHALL:

EXPOSE EXISTING UTILITIES PRIOR TO TRENCHING TO VERIFY THE ALIGNMENTS AND ELEVATIONS OF THE UTILITIES, AND TO VERIFY DESIGN ASSUMPTIONS. EXISTING UTILITIES MAY REQUIRE RELOCATION AND/OR PROPOSED IMPROVEMENTS MAY REQUIRE GRADE OR ALIGNMENT REVISION DUE TO FIELD CONDITIONS. IF THE EXPOSED UTILITY IS DETERMINED TO BE IN A LOCATION WHICH IS NOT REFLECTED BY THE CONSTRUCTION DOCUMENTS, NOTIFY THE ENGINEER IN WRITING SO THAT APPROPRIATE ADJUSTMENTS CAN BE MADE.

REPORT UTILITY CONFLICTS TO THE OWNER'S REPRESENTATIVE IN WRITING AS THEY ARE ENCOUNTERED SO THAT THE OWNER AND OWNER'S REPRESENTATIVE CAN MAKE A DECISION AS TO HOW THE CONTRACTOR SHOULD PROCEED WITH THE WORK.

COORDINATE WITH UTILITY COMPANIES, FURNISH, INSTALL, TEST AND OBTAIN INSPECTIONS FOR UNDERGROUND IMPROVEMENTS PRIOR TO SURFACING.

UNLESS OTHERWISE, PROVIDE ADS N12 OR EQUIVALENT HDPE PIPE NOTED WHERE ANNOTATED AS STORM DRAIN (SD) ON THIS DRAWING.

PROVIDE TRENCHING FOR SANITARY SEWER UTILITIES IN ACCORDANCE WITH ROSS VALLEY SANITARY DISTRICT STANDARD SPECIFICATIONS AND DRAWINGS AND FOR OTHER UTILITIES IN ACCORDANCE WITH THE UNIFORM CONSTRUCTION STANDARDS OF THE CITIES AND COUNTY OF MARIN DRAWING NUMBERS 330, 340 AND 350.

COORDINATE WITH UTILITY COMPANIES, FURNISH, INSTALL, TEST AND OBTAIN INSPECTIONS FOR UNDERGROUND IMPROVEMENTS PRIOR TO SURFACING.

OTHER FORCES WILL BE ENGAGED IN INSTALLING, IN MAKING ADJUSTMENTS TO AND/OR IN RELOCATING VARIOUS FACILITIES THROUGHOUT THE PROJECT. THE CONTRACTOR SHALL COORDINATE WORK AROUND OTHER FORCES IN A MANNER THAT DOES NOT PROLONG THE CONTRACT TIME.

EXISTING UNDERGROUND FACILITIES SHOWN ON THESE DRAWINGS ARE APPROXIMATE AND HAVE BEEN LOCATED BASED ON TOPOGRAPHIC FEATURES AND AVAILABLE INFORMATION. THE PROFESSIONAL WHO PREPARED THESE DRAWINGS, THE OWNER, AND THE COUNTY OF MARIN ASSUME NO RESPONSIBILITY FOR THE ACCURACY OF THESE FACILITIES OR FOR THE INADVERTENT OMISSION OF RELATED INFORMATION.

THE CONTRACTOR IS CAUTIONED NOT TO ORDER PRECAST ITEMS OR INSTALL IMPROVEMENTS UNTIL CONFLICTS ARE RESOLVED. IMPROVEMENTS INSTALLED OR ORDERED PRIOR TO CONFLICT RESOLUTION SHALL BE DONE SOLELY AT THE CONTRACTOR'S RISK AND AT NO EXPENSE TO THE OWNER, THE DESIGN PROFESSIONAL, THE TOWN OF MARIN, OR THE COUNTY OF MARIN.

UTILITY CONFLICTS MAY OCCUR IN THOSE INSTANCES WHERE TWO GRAVITY UTILITIES CROSS AND LACK THE REQUIRED SEPARATION, OR IN THOSE INSTANCES WHERE AN EXISTING UTILITY HAS NOT BEEN IDENTIFIED IN THE CONSTRUCTION DOCUMENTS.

CROSSING UTILITIES WHICH HAVE BEEN IDENTIFIED IN THE CONSTRUCTION DOCUMENTS MAY NOT BE CONSTRUED AS UTILITY CONFLICTS. THE CONTRACTOR SHALL INSTALL GRAVITY UTILITIES TO THE LINES AND ELEVATIONS IDENTIFIED IN THE CONSTRUCTION DOCUMENTS AND INSTALL OTHER UTILITIES ABOVE OR BELOW GRAVITY UTILITIES WHILE COMPLYING WITH THE MINIMUM COVER REQUIREMENTS FOR EACH UTILITY INSTALLED.

EARTHWORK:

EARTHWORK QUANTITIES ARE APPROXIMATE AND HAVE BEEN SUMMARIZED ON THESE DRAWINGS TO PROVIDE THE REVIEWING AGENCY WITH AN OPINION OF HOW MUCH MATERIAL MAY BE MOVED TO FACILITATE THE PROPOSED IMPROVEMENTS.

Table with 2 columns: Description, Quantity. Includes rows for Disturbed Area (0.41 acres), Soil Moved on Site (260 cubic yards), and Fill (330 cubic yards).

\*SOIL MOVED ON SITE IS ANY SOIL EXCAVATED (CUT) AS A RESULT OF STRIPPING OR GRADING ACTIVITIES AND REUSED ON THE PROJECT SITE AS FILL.


Table with 2 columns: Description, Quantity. Includes rows for Total Pre-Project Impervious (215 squared feet), Total Post-Project Impervious (6,200 squared feet), and Total Impervious (6,415 squared feet).

SITE IMPROVEMENT DRAWINGS FOR

ADVANCED BUILDING SOLUTIONS RESIDENCE SAN ANSELMO MARIN COUNTY, CALIFORNIA

APN 177-051-08

APRIL 2023



VICINITY MAP NOT TO SCALE

INDEX OF DRAWINGS

- C1. PROJECT INFORMATION
C2. GRADING & UTILITY PLAN
C3. EROSION & SEDIMENT CONTROL PLAN

SYMBOLS & LEGEND

Legend defining symbols for existing and proposed features including benchmarks, pipes, valves, fences, utilities, and materials. Includes a cross-section identification symbol.

DEVELOPER: ADVANCED BUILDING SOLUTIONS
CIVIL ENGINEER: BKF ENGINEERS
ARCHITECT: POLSKY PERLSTEIN ARCHITECTS
LANDSCAPE ARCHITECT: IMPRINTS LANDSCAPE ARCHITECTURE
GEOTECHNICAL ENGINEER: KC ENGINEERING COMPANY

ABBREVIATIONS

Table of abbreviations for construction terms such as MAX, MIN, MON, NTS, OVH, etc.

TOPOGRAPHIC NOTES

UNAUTHORIZED CHANGES & USES: THE PROFESSIONAL PREPARING THIS MAP WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO OR USES OF THIS MAP...

THE LOCATIONS OF EXISTING UNDERGROUND FACILITIES SHOWN ON THESE DRAWINGS ARE APPROXIMATE AND ARE BASED ON OBSERVED TOPOGRAPHIC SURFACE FEATURES AND AVAILABLE INFORMATION...

CONTOURS HAVE BEEN INTENTIONALLY OMITTED FROM THIS DRAWING FOR CLARITY, BECAUSE THE SITE IS RELATIVELY FLAT, AND THEY WILL NOT PROVIDE ANY DISCERNABLE ADDITIONAL INFORMATION.

TREE DIAMETERS ARE MEASURED AT CHEST HEIGHT (48"). DRIPLINE DIAMETERS AND TREE SPECIES ARE APPROXIMATE ONLY AND SHOULD BE VERIFIED BY A CERTIFIED ARBORIST.

BOUNDARY, EASEMENT AND SETBACK INFORMATION SHOWN HEREON WAS OBTAINED PRELIMINARY TITLE REPORT CAL LAND TITLE ON SEPTEMBER 1 2022, MARIN COUNTY RECORDS.

BASIS OF BEARINGS: RECORD OF SURVEY OF THE LANDS OF HAMILTON, FILED FOR RECORD IN BOOK 2009 OF MAPS, AT PAGE 120, MARIN COUNTY RECORDS.

THE BEARINGS AND DISTANCES DO NOT REFLECT A FIELD SURVEY AND DO NOT CONSTITUTE A FORMAL BOUNDARY DETERMINATION.

BENCHMARK: SQUARE BOLT IN MONUMENT WELL IN FAWN DRIVE, LOCATION SHOWN HEREON. ELEVATION: 136.48 (DATUM NAVD 88 BASED ON GPS OBSERVATION).

FIELD SURVEY DATE: 10/17/2022

GENERAL NOTES


THE PROPOSED DEVELOPMENT WILL BE IN CONFORMANCE WITH THE CITY OF SAN RAFAEL ZONING CODE, GENERAL PLAN AND DESIGN & CONSTRUCTION STANDARDS OR AS APPROVED BY THE REVIEWING AGENCY.

- WATER SUPPLY: ----MARIN MUNICIPAL WATER DISTRICT
SEWAGE DISPOSAL: ----ROSS VALLEY SANITARY DISTRICT
PRESENT ZONING: ----R1-BD RESIDENTIAL SINGLE FAMILY
PROPOSED ZONING: ----R1-BD RESIDENTIAL SINGLE FAMILY


GRADING NOTES

SOILS ON THIS SITE ARE NOT ANTICIPATED TO PROHIBIT THIS TYPE OF DEVELOPMENT.

PROVISIONS FOR EROSION CONTROL WILL BE INCORPORATED INTO THIS PROJECT.



BKF ENGINEERS
1646 N. CALIFORNIA BLVD.
SUITE 400
WALNUT CREEK, CA 94596
(925) 940-2200
www.bkf.com





ADVANCED BUILDING SOLUTIONS RESIDENCE
APN 177-051-08
SAN ANSELMO, CALIFORNIA
PROJECT INFORMATION

Table with columns for Date, Scale, Design, Drawn, Approved, Job No., and Revisions. Includes drawing number C1 and page 1 of 3.







**SEDIMENT CONTROL NOTES**

EROSION AND SEDIMENT CONTROL MEASURES SHOWN ON THESE DRAWINGS ARE GENERAL IN NATURE AND MAY NOT BE APPLICABLE DURING CERTAIN PHASES OF CONSTRUCTION. THE CRUSHED ROCK ENTRANCE DETAIL SHOWN ON THESE DRAWINGS REFLECTS A CONDITION PRIOR TO SURFACES BEING PAVED, WHEREAS FILTERS AT STORM WATER INLETS REFLECTS A CONDITION AFTER THE STORM DRAIN SYSTEM HAS BEEN INSTALLED.

THE CONTRACTOR SHALL INTEGRATE APPROPRIATE MEASURES DURING EACH CONSTRUCTION PHASE TO ENSURE THAT SEDIMENT AND OTHER POLLUTANTS DO NOT ENTER THE STORM DRAIN SYSTEM.

THE CONTRACTOR SHALL USE WATER OR DUST PALLIATIVE TO MINIMIZE WIND EROSION. THE CONTRACTOR SHALL DESIGNATE AN AREA ON SITE TO STOCKPILE MATERIAL. THE STOCKPILED MATERIAL SHALL BE COVERED AT ALL TIMES TO PREVENT EROSION FROM WIND, RAIN AND STORM WATER RUNOFF.

EROSION AND SEDIMENT CONTROL MEASURES SHALL BE PLACED IN FRONT OF INCOMPLETE STORM DRAIN SYSTEMS TO PREVENT DEBRIS AND SEDIMENT-LADEN WATER FROM ENTERING INTO THE PUBLIC STORM DRAIN SYSTEM. BEST MANAGEMENT PRACTICES SHALL BE USED WHEN INSTALLING SUCH DEVICES.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTANT MAINTENANCE OF EROSION AND SEDIMENT CONTROL MEASURES AT ALL TIMES TO THE SATISFACTION OF THE OWNER, AND COUNTY OF MARIN. EROSION AND SEDIMENT CONTROL MEASURES AND THEIR INSTALLATION SHALL BE ACCOMPLISHED USING BEST MANAGEMENT PRACTICES.

IF THE STORM DRAIN SYSTEM IS NOT INSTALLED PRIOR TO A PRECIPITATION EVENT, ADDITIONAL MEASURES SHALL BE TAKEN SUCH AS TEMPORARY SETTLING BASINS WHICH MEET THE SATISFACTION OF THE OWNER, AND THE COUNTY OF MARIN. SILT AND/OR CATCH BASINS MUST BE CLEANED OUT ON A REGULAR BASIS AFTER STORMS TO MAINTAIN DESIGN CAPACITY.

STORM WATER RUNOFF FROM THE CONSTRUCTION SITE SHALL BE DIRECTED TOWARD AN INLET WITH A SEDIMENT OR FILTRATION INTERCEPTOR PRIOR TO ENTERING THE STORM DRAIN SYSTEM.

THE CONTRACTOR WILL BE RESPONSIBLE FOR CLEANING WATER THAT HAS BECOME POLLUTED DUE TO NOT TAKING NECESSARY EROSION AND SEDIMENT CONTROL ACTIONS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANUP OF MUD AND DEBRIS CARRIED ONTO SURROUNDING STREETS AND ROADS AS A RESULT OF CONSTRUCTION ACTIVITY ON THE SITE TO THE SATISFACTION OF THE COUNTY OF MARIN.

ANY DENUDED OR DISTURBED SOILS SHALL BE PROTECTED USING BEST MANAGEMENT PRACTICES.

PRIOR TO AND DURING A PRECIPITATION EVENT, ALL PAVED AREAS WILL BE KEPT CLEAR OF EARTH MATERIAL AND DEBRIS. THE SITE IS TO BE MAINTAINED BY THE DEVELOPER, CONTRACTOR OR OWNER SO THAT A MINIMUM OF SEDIMENT-LADEN RUNOFF LEAVES THE SITE.

THE CONTRACTOR SHALL INFORM ALL CONSTRUCTION SITE WORKERS ABOUT THE MAJOR PROVISIONS OF THE EROSION AND SEDIMENT CONTROL PLAN AND SEEK THEIR COOPERATION IN AVOIDING THE DISTURBANCE OF THESE CONTROL MEASURES.

BEST MANAGEMENT PRACTICES SHALL BE VISUALLY MONITORED ON A WEEKLY BASIS DURING THE DRY SEASON AND RECORDED IN AN INSPECTION CHECKLIST. RAIN EVENT VISUAL MONITORING SHALL BE PERFORMED WITHIN 48 HOURS PRIOR TO AN ANTICIPATED RAIN EVENT, DAILY DURING A RAIN EVENT AND WITHIN 48 HOURS FOLLOWING A RAIN EVENT. REMOVE SEDIMENTS WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE BARRIER AND REPLACE FILTER DEVICES AS NECESSARY TO ENSURE PROPER FUNCTION.

UNSTABILIZED AREAS WILL BE REPAIRED AS SOON AS POSSIBLE AFTER BEING DAMAGED.

ALL GRADED OR DISTURBED AREAS SHALL BE STABILIZED IMMEDIATELY AFTER GRADING IS COMPLETE.

ENTRANCE TO THE PROJECT SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT INTO PUBLIC RIGHT-OF-WAY. WHEN NECESSARY, WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE OF PUBLIC RIGHTS-OF-WAY. WHEN WASHING IS REQUIRED IT SHALL BE DONE IN AN AREA STABILIZED WITH CRUSHED ROCK THAT DRAINS INTO A SEDIMENT TRAP.

ALL SEDIMENT SPILLED, DROPPED, OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY SHALL BE REMOVED IMMEDIATELY USING BEST MANAGEMENT PRACTICES.

ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR PURPOSE SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.

ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REPAIRED OR REPLACED WHEN THEY ARE NO LONGER FUNCTIONING.

THE CONTRACTOR SHALL HAVE EROSION AND SEDIMENT CONTROL MEASURES ON SITE ADEQUATE TO PROTECT THE ENTIRE SITE SUCH THAT IT IS IMMEDIATELY AVAILABLE IN PREPARATION OF A PRECIPITATION EVENT.


THE CONTRACTOR SHALL DISPOSE OF UNUSED CONSTRUCTION MATERIALS AND WASTE PRIOR TO THE COMPLETION OF CONSTRUCTION.

AFTER CONSTRUCTION IS COMPLETE ALL STORM DRAIN SYSTEMS ASSOCIATED WITH THIS PROJECT SHALL BE INSPECTED AND CLEARED OF ACCUMULATED SEDIMENTS AND DEBRIS.


GRADED AREAS TO BE SEEDED FOR EROSION CONTROL SHALL USE GRASS SEED AT THE RATE OF 75-100/LBS. PER ACRE. SEEDED AREAS SHALL BE IRRIGATED TO ENSURE COVER IS ESTABLISHED PRIOR TO THE RAINY SEASON.

HYDROSEED SHALL BE EITHER APPLIED MECHANICALLY OR BY HYDROSEEDING. HYDROSEEDING REQUIRES THE APPLICATION OF FIBER AND STABILIZING EMULSION. MECHANICAL APPLICATION SHALL REQUIRE ROLLING, TAMPING, OR OTHERWISE WORKING THE SEED APPROXIMATELY 0.5 INCHES INTO THE TOPSOIL.


STABILIZATION OF EXPOSED GRADED AREAS WITH STRAW MULCH SHALL BE APPLIED AT A RATE OF 2 TONS PER ACRE.




**FIBER ROLL DETAIL**  
NTS



**TYPICAL SEDIMENT DEVICES**  
NTS




**GRAVEL BAG**  
NTS



**CONCRETE WASHOUT DETAIL**  
NTS

- NOTES:
1. LOCATION IN PLAN SHOWN FOR GRAPHIC PURPOSE ONLY. LOCATION TO BE APPROVED BY INSPECTOR.
  2. CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 30 FT. OF THE TEMPORARY CONCRETE WASHOUT FACILITY.
  3. CONSTRUCT A BERMED AREA LARGE ENOUGH FOR LIQUID AND WASTE CONCRETE MATERIALS GENERATED DURING WASHOUT PROCEDURES. WASHOUT WASTES INTO THE TEMPORARY WASHOUT WHERE THE CONCRETE CAN SET, BE BROKEN UP, AND THEN DISPOSED PROPERLY. WASHOUT SHOULD BE LINED WITH A 10 MIL PLASTIC SO THERE IS NO DISCHARGE INTO THE UNDERLYING SOIL. REFER TO PROJECT SWPPP FOR BMP INSPECTION AND MAINTENANCE.



**BKF ENGINEERS**  
1646 N. CALIFORNIA BLVD.  
SUITE 400  
WALNUT CREEK, CA 94596  
(925) 940-2200  
www.bkf.com

**WJB**  
WILLIAM J. BORIO  
04-04-2023  
C 75905

**ADVANCED BUILDING SOLUTIONS RESIDENCE**  
APN 177-051-08  
SAN ANSELMO, CALIFORNIA

**EROSION & SEDIMENT CONTROL PLAN**

Revisions	No.	Date	By	Check
	1	APR 2023	AS SHOWN	RHS
	2		DESIGN	RHS
	3		DRAWN	IT/AM
	4		APPROVED	RHS

Job No: 20220285-12



